

15-051-00857-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
311 No. Broadway
Wichita, Kansas

Ellis County, Sec. 36 Twp. 11 Rge. 16 (E) (W)X

Location as "NE/CNW/SE/SW" or footage from lines NW NW SW

Lease Owner Olmar Oil Co.

Lease Name Wagner Well No. #1

Office Address 820 Union National Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 9-20-62 19

Plugging completed 9-25-62 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3430 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	238	
				5-1/2	3430	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded at 3330' mixed and dumped 4 sacks cement.
Mixed and pumped 33 sacks of mud at 500' - pulled 2 joints.
Mixed and pumped 20 sacks cement at 440' - pulled 8 joints.
Mixed and pumped 20 sacks cement - pulled 8 joints.
Capped hole with 10 sacks.

RECEIVED
OCT 1 1962
10-01-1962

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.

Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton

Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.

Box 364, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 28 day of Sept., 1962

My commission expires 24 October 1964

Sidney D. Miller Notary Public.

15-051-00857-00-00

DRILLER'S LOG

Company: Petroleum Management Co.

NW-NW-SW

Farm: Wagner Well No: 1

Sec: 36, Twn: 14, Rge: 16

Total Depth: 3430'

County: Ellis, Kansas

Comm: 3/29/56 Comp: 4/7/56

Contractor: Peel Brothers, Inc.

Elevation:

Casing:

8 5/8" • 238' Gen.
5 1/2" • 3430' Gen.

Production:

Figures below indicate bottom of formation

Shale and post rock	0'	40'
Shale and sand streaks		150
Shale and shells		450
Shale		475
Sand		600
Shale		700
Red bed		982
Anhydrite		1095
Red bed, shale and shells		1700
Lime and shale		3153
Lime		3400
Artuskie		3430
Total Depth		3430

RECEIVED
STATE CORPORATION COMMISSION
10-04-1962
OCT 4 1962
CONSERVATION DIVISION
Wichita, Kansas

This is to certify that the above information is to the best of my knowledge true and correct.

PEEL BROTHERS, INC.

BY Paul J. Peel

SUBSCRIBED AND SWORN TO before me this 11 day of April 1956

My commission expires September 25, 1957

Norman L. Kase
Notary Public