

STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-169-00704-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH


Locate well correctly on above  
Section Plat

Saline

County. Sec. 6 Twp 14 Rge. 2 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE/4 SW/4 SE/4  
Lease Owner Stearns Petroleum Co.  
Lease Name Stearns Petroleum Co-Kohler Well No. 1  
Office Address Russell, Kansas.  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed November 21, 1954 19\_\_\_\_  
Application for plugging filed January 5, 1955 19\_\_\_\_  
Application for plugging approved January 5, 1955 19\_\_\_\_  
Plugging commenced January 10 1955  
Plugging completed January 19 1955  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes.

Name of Conservation Agent who supervised plugging of this well Rhule Durkey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3230 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3230 feet to Surface feet for each plug set.

Hole filled with sand from bottom (3230 Ft) to 3185 feet; Six sacks of cement placed in hole with dump bailer to form 48 foot cement from 3137 ft; Halliburton pump truck thereafter pumped in 30 sacks of weight mud and 30 sacks of cement into hole with plug on top of cement, and plug pumped down to 100 feet; hole bailed dry, and hole filled with mud from 100 feet to 25 feet; Hole filled to surface with ten sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes and Sons Pipe Pulling Co  
Address Russell, Kansas.

STATE OF \_\_\_\_\_, COUNTY OF \_\_\_\_\_, SS.  
\_\_\_\_\_, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

SUBSCRIBED AND SWORN TO before me this 25th day of January, 1955

My commission expires April 5, 1958 \_\_\_\_\_ Notary Public.

**PLUGGING**  
FILE SEC 6-14-R2W  
BOOK PAGE 88 LINE 42

JAN 25 1955  
01-26-1955  
CONSERVATION DIVISION  
WICHITA, KANSAS

15-169-00704-00-00

KOHLER #1 WELL

Operator: Corum and Crosswy  
Contractor: Stearns Petroleum, Inc.  
Commencement Date: November 11, 1954  
Completion Date: November 21, 1954

LOCATION: NE SW SE  
Section 6-14S-2W,  
Saline County, Kansas

Casing Record:

8 5/8" - Cemented with 150 sacks.  
5 1/2" - Set at 3230' - Cement with 125 sacks.

- WELL LOG -

Surface Clay	0	40
Sand	40	100
Sand and Shale	100	155
Lime and Shale	155	710
Shale and Lime Shells	710	1014
Shale and Shells	1014	1575
Shale and Lime Shells	1575	1780
Shale and Lime	1780	2240
Lime	2240	2290
Lime and Shale	2290	2500
Lime	2500	2595
Shale and Lime	2595	2778
Lime and Chert	2778	2813
Lime	2813	2835
Lime and Shale	2835	3029
Sand and Lime	3029	3083
Lime and Shale	3083	3230
Viola	3191	
Total Depth:	3230	

STATE OF KANSAS )  
                          ) SS:  
COUNTY OF RUSSELL )

I hereby certify that the above information is true and correct to the best of my knowledge.

SUBSCRIBED AND SWORN to before me, this 12<sup>th</sup> day of December

19 54.

Betty Law Miller  
Notary Public

My Commission Expires:

April 5-1958

**PLUGGING**  
WELL SEC 6-14-2W  
BOOK PAGE 18 LINE 42

RECORDED  
INDEXED  
01-26-1955  
SALINE COUNTY, KANSAS