

STATE CORPORATION COMMISSION


Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 311 No. Broadway
 Wichita, Kansas

15-169-00227-00-00
 WELL PLUGGING RECORD

Salina County, Sec. 10 Twp. 14 Rge. 2 (E) (W)

Location as "NE/CNWSW" or footage from lines CW/2 SW/4 NW/4
 Lease Owner Don McKellar
 Lease Name Hattison Well No. 1
 Office Address 1321 Pershing, Salina, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed May 6, 1962
 Application for plugging filed May 6, 1962
 Application for plugging approved May 6, 1962
 Plugging commenced May 6, 1962
 Plugging completed May 6, 1962
 Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones, McPherson, Kansas
 Producing formation none Depth to top _____ Bottom _____ Total Depth of Well 3175 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Fresh water zone		30'	60'	8 5/8	154'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole at 160 ft., put 25 sacks cement on top of plug.

Second plug at 30 ft., put 8 sacks cement on top of plug.

2 sacks, in rathole.

RECEIVED
 STATE CORPORATION COMMISSION

MAY 1 - 1962
 05-15-1962
 CONSERVATION DIVISION
 WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Blackstone Drilling, Inc.
 Address Peoples Bank Bldg., McPherson, Kansas

STATE OF Kansas COUNTY OF McPherson
Owner & operator

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and that the above-described well as filed and that the same are true and correct, so help me God.

(Signature) Don McKellar
 Don McKellar, Salina, Kansas
 1321 Pershing, (Address)

SUBSCRIBED AND SWORN TO before me this 10th day of May, 1962

My commission expires September 5, 1964
Myrtle D. Beeghly Notary Public.

15-169-00237-00-00

Blackstone Drilling, Inc.

P. O. BOX 455 • PHONE CH 1-1250

McPHERSON • KANSAS

May 8, 1962

COMPANY: DON MC KELLAR
CONTRACTOR: BLACKSTONE DRILLING, INC.
FARM: MATTISON # 1
LOCATION: C-W/2 SW/4 NW/4, Sec. 10-14-2W
Saline County, Kansas
COMMENCED: APRIL 25, 1962
COMPLETED: MAY 6, 1962
ELEVATION: 1202 K.B.

0	to	30	Sand
30	to	60	Clay
60	to	70	Sand
70	to	151	Lime
151	to	1185	Lime & Shale
1185	to	1530	Shale & Shells
1530	to	1924	Shale & Lime
1924	to	2205	Lime
2205	to	2330	Lime & Shale
2330	to	2435	Lime
2435	to	2592	Shale & Lime
2592	to	2690	Mississippi Chert
2690	to	2760	Chert & Lime
2760	to	2910	Lime & Shale
2910	to	2920	Shale
2920	to	3000	Lime & Chert
3000	to	3046	Lime
3046	to	3075	Lime
3075	to	3155	Shale
3155	to	3165	Viola Lime
3165	to	3175	Lime
		3175	T. D.

OK-18-1962
KANSAS


Cut 12 1/4 in. hole - run 154 ft. of 8 5/8 in. Casing and cemented on bottom with 115 sacks cement. Cut 7 7/8 in. hole. Hole Dry and Abandoned. Plugged hole at 160 ft. put 25 sacks cement on top of plug. Second plug at 30 ft. put 8 sacks cement on top of plug. Put 2 sacks in rathole. Hole plugging completed at 10:00 A.M., May 6, 1962 by Cecil Jones, State Plugger, McPherson, Kansas.

TOPS: Kansas City - 1924' Mississippi - 2592' Hunton - 2922'
Maquoketa Shale - 3043' Maquoketa Dolomite - 3146' Viola - 3155'

Measurements taken from K. B.

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc., do hereby certify that the above and foregoing is a true and correct copy of log on the Mattison # 1, located on Sec. 10-14-2W, Saline County, Kansas as reflected by files of the Blackstone Drilling, Inc.


H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public, within and for McPherson County, Kansas this 8th day of May, 1962.


Ruth McVay, Notary Public

My Commission Expires: 12/18/65