

15-169-30028-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Saline County, Sec. 13 Twp. 14S Rge. (X) 2 (W)
Location as "NE/CNW&SW" or footage from lines SE SE NW
Lease Owner Graves-Phillips-Brunson-Spines
Lease Name Weber Well No. 1
Office Address 412 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 21, 1966
Application for plugging filed March 21, 1966
Application for plugging approved March 21, 1966
Plugging commenced March 21, 1966
Plugging completed March 21, 1966
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman, Holyrood, Kansas
Producing formation Depth to top Bottom Total Depth of Well 2778 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	219	

RECEIVED
CORPORATION COMMISSION
MAR 31 1966
03 31 1966
WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 210 feet. Followed by wooden plug and 1/2 sack hulls. Placed 25 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/4 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.
Address 412 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.
John C. Graves (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Phillips Graves*
412 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of March, 1966

My commission expires April 30, 1967 Betty Brandt Notary Public.

15-169-30028-00-00

R O T A R Y D R I L L E R S ' L O G

OPERATOR: Graves-Phillips-Brunson-Spines DRILLING COMMENCED: March 17, 1966
412 Union Center
Wichita, Kansas

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: March 21, 1966
412 Union Center
Wichita, Kansas

CASING RECORD: 11 Jts. 219' 8-5/8" cemented with 180 sacks
LOCATION: Weber No. 1
SE SE NW
Section 13-14S-2W
Saline County, Kansas

0 - 220	Shale & lime
220 - 314	Lime
314 - 835	Lime & shale
835 - 1265	Shale & lime
1265 - 1675	Shale
1675 - 1796	Lime
1796 - 1830	Shale
1830 - 1996	Sand & sandy shale
1996 - 2362	Lime
2362 - 2656	Lime & shale
2656 - 2718	Lime
2718 - 2778	Chert & lime
2778	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION

MAR 31 1966
03-31-1966
CONSERVATION DIVISION
WICHITA, KANSAS

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By Phil Graves
President

STATE OF KANSAS)
) SS:
BUTLER COUNTY)

Subscribed and sworn to before me, a Notary Public, this 29th of March, 1966.

Betty Brandt
Betty Brandt Notary Public

My commission expires:
April 30, 1967