


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ellsworth County, Sec. 1 Twp. 14 Rge. (E) 6 (W)
Location as "NE/CNW&SW" or footage from lines NE SW SE
Lease Owner Leo J. Drilling Oil Company
Lease Name Yordy Well No. #1
Office Address Victoria, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 25 19 57
Application for plugging filed October 25 19 57
Application for plugging approved 19
Plugging commenced October 24 19 57
Plugging completed October 24 19 57
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	245'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged @ 230' with 15 sacks of cement. Plug @ 25' with 5 sacks of cement, job completed at 5:00 P. M. on October 24, 1957.

RECEIVED
STATE CORPORATION COMMISSION
DEC 16 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Strata Drilling, Inc.
Address Box 355, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Jim B. McWilliams (employee of owner) or (owner of property) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim B. McWilliams
Jim B. McWilliams
Box 355, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of December, 19 57

My commission expires November 9, 1959
Robert E. Southern
Robert E. Southern Notary Public.

PLUGGING
FILE SEC 1 T 14 R 6W
BOOK PAGE 57 LINE 15

15-053-00127-00-00

D R I L L E R S L O G

#1 Yordy

CASING RECORD:
245' of used 8-5/8"
surface casing

COMPANY: Leo J. Drilling Oil Co.

DESCRIPTION:
NE SW SE
Sec. 1-14S-6W
Ellsworth Co., Kansas

TOTAL DEPTH:
3718'

COMMENCED: October 15, 1957
COMPLETED: October 24, 1957

ELEVATION: 1473' RB
1468' GL

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Sand	0	75	Ran 245' used 8-5/8" surface casing; cemented w/150 sacks of cement & 2% c. c.
Shale	75	245	
Shale & Red Bed Strs.	245	400	
Shale & Shells	400	560	
Shale	560	700	
Anhydrite	700	740	
Shale & Shells	740	895	
Shale, Lime & Shells	895	1070	
Shale & Lime	1070	1800	
Shale & Shells	1800	2055	
Lime & Shale	2055	2500	
Lime	2500	3718	

TOTAL DEPTH 3718'

Top Anhydrite	700'	
Top Heebner	2380'	(- 907)
Top Toronto	2398'	(- 925)
Top Douglas	2425'	(- 952)
Top Brown Lime	2498'	(-1025)
Top Lansing	2557'	(-1084)
Top Mississippi	3248'	(-1775)
Top Hunton	3360'	(-1887)
Top Viola	3531'	(-2058)
Top Simpson	3609'	(-2136)

CONSERVATION

STATE OF KANSAS)
) ss:
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Jim B. McWilliams
Jim B. McWilliams, Sec-Tres.

Subscribed and sworn to before me this 12th day of December, 1957.

Robert E. Southern
Robert E. Southern Notary Public

My Commission Expires:
November 9, 1959

PLUGGING
FILE NO. 14-14-164
BOOK PAGE 571 E 15