

15-063-30092-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Gove County. Sec. 32 Twp. 14S Rge. (E) 27 (W)
Location as "NE/CNW/SE/SW" or footage from lines G NE NW
Lease Owner Pickrell Drilling Company
Lease Name Mendenhall "G" Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 23, 1966
Application for plugging filed September 23, 1966
Application for plugging approved September 23, 1966
Plugging commenced September 23, 1966
Plugging completed September 23, 1966
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. W. L. Nichols, Moreland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4391 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	247'	None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 240'. Set plug. Cemented with 20
sacks cement. Heavy mud to 40'. Set plug. Cemented
with 10 sacks cement to bottom of cellar. Plugged
rat hole with 2 sacks cement.

Stamp: OCT 5 1966
Stamp: CONSERVATION DIVISION
Stamp: WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas


STATE OF KANSAS COUNTY OF SEDGWICK ss.
G. W. SEBITS (employee, contractor or owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. W. Sebits
705 Fourth National Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of October, 1966

My commission expires May 10, 1970 L. M. Whiting Notary Public.



15-063-30092-00-00

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
 705 Fourth National Bank Bldg.
 Wichita, Kansas
 Rotary Drilling Commenced 9-14-66

LOCATION: Mendenhall "C" No. 1
 C NE NW Section 32-14S-27W
 Gove County, Kansas
 Rotary Drilling Completed 9-23-66

CONTRACTOR: **PICKRELL DRILLING COMPANY**
 Wichita, Kansas

CASING RECORD: (12 Jts.) 8 5/8" surface casing set at 247' and cemented with 160 sacks cement. Circulated. Completed at 3:45 PM, September 14, 1966. No oil string run. D. & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

60	Sandy Clay	<u>C. F. S.</u>
248	Shale & Shells	3947
1275	Gray Shale & Sand	3977
1785	Shale, Sand & Lime	4250
2035	Shale & Shells	4307
3810	Lime & Shale	4335
3925	Lime	4370
3993	Kansas City	4391
4075	Lime	
4310	Lime & Shale	
4350	Lime	
4391	Mississippian, RTD	

	<u>Slope Tests</u>
	2500
	3000
	3500
	4000

	<u>S. L. M.</u>
	3417

STANDARD OIL COMPANY
 OCT 1 1966
 CORRELATION DIVISION
 Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
 By [Signature]
 C. W. SEBITS, Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 3rd day of October, 1966, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

[Signature]
 L. M. Whiting, Notary Public