


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Logan County, Sec. 17 Twp. 13 Rge. 34W (E) (W)
Location as "NE/CNW&SW" or footage from lines G SE SW
Lease Owner Wycoff Brothers Oil Company
Lease Name Molby Well No. A-1
Office Address Russell Springs, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D&A
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ 19____
Plugging completed October 4, 19 63
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4725' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

102' -- 8 5/8" Surface pipe, cement circulated with 85 sacks.
Circulated hole with heavy mud, set plug at 120' with 1/4 sack hulls
and displaced 25 sacks cement through drill pipe. Heavy mud to 40'
set plug with 1/2 sack hulls and 10 sacks cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

APR 28 1964

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor S & C Drilling Company, Inc.
Address Box 271 Hays, Kansas

STATE OF Kansas COUNTY OF Logan, ss.
Richard Wycoff (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Richard Wycoff
Russell Springs Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of April, 1964

My commission expires Dec. 5 1964
Marion K. Wycoff Notary Public.

CERTIFIED DRILLER'S LOG

COMPANY: Wycoff Bros. Oil Co.

LEASE: Molby #1^{"A"}

CONTRACTOR: S. & C. Drlg, Inc.

LOCATION: C SE SW Sec. 17-13S-34W

COMMENCED UNDER SURFACE:

Logan County, Kans.

8-22-63. Drilled to 3292', twisted off.
Skidded 30' east. Set surface on new
location 9-11-63

COMPLETED: 10-~~8~~⁴-63CASING RECORD: 102' of 8-5/8".
Cemented with 80 sks.

ELEVATION: 3,002 K.B.

POTENTIAL: D & A

FIGURES DENOTE BOTTOM OF FORMATION. THESE ARE K.B. MEASUREMENTS,
WHICH IS GROUND LEVEL PLUS 5'.

<u>FORMATION</u>	<u>DEPTH</u>
Shale	695
Lime & Shale	750
Shale	825
Shale & Shells	1120
Shale	1460
Shale & Sand	1570
Hard Rock	1590
Shale w/sand & lime	1870
Shale w/ anhydrite streaks	2050
Shale w/ hard sand	2215
Red Bed & Shale	2360
Red Bed	2405
Anhydrite	2478
Shale & Red Bed	2570
Shale w/lime streaks	2823
Shale & Lime	3235
Lime	3430
Lime & Shale	3840
Lime w/ shale streaks	3908
Lime & Shale	3980
Lime	4310
Lime & Shale	4350
Lime & Chert	4387
Lime	4412
Lime w/ shale streaks	4470
Lime & Shale	4500
Lime	4525
Lime & Sand	4527
Lime & Shale	4565
Lime	4725 T.D.

I hereby certify that this is a true and correct copy of the above
log to the best of my knowledge.

By: *D. J. Sullivan*
D. J. Sullivan

S. and C. Drilling, Inc.