

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-109-20.661-00-00

LEASE NAME Wieland

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Coas. Div.  
office within 30 days.

WELL NUMBER 1-18

1240 Ft. from S Section Line

1050 Ft. from W Section Line

SEC. 18 TWP. 13S RGE. 32 (E) or (W)

COUNTY Logan

Date Well Completed 11-19-97

Plugging Commenced 11-18-97

Plugging Completed 11-19-97

LEASE OPERATOR Brito Oil Company, Inc.

ADDRESS 120 S. Market, Suite #400, Wichita, KS 67202

PHONE#(316) 263-8787 OPERATORS LICENSE NO. 4629

Character of Well D/A

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-18-97 (date)

by Ed Schumaker (KCC District Agent's Name).

Is ACO-1 filed? Enclosed If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Fill with heavy mud. 1st plug from 2530'-2430' with 25 sks, 2nd plug from 1485'-1085' with 100 sks, 3rd plug from 270'-110' with 40 sks, 4th plug from 40'-0' with 10 sks, 15 sks in rat hole. Total of 190 sks, 60/40 pos, 6% gel, 1/4# floseal per sk.

12-17-97

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brito Oil Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Raul F. Brito, President

(Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: that I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) \_\_\_\_\_

(Address) 120 S. Market, #400, Wichita, KS 67202



AND SWORN TO before me this 2nd day of December, 19 97

Betty M. Abbott  
Notary Public

My Commission Expires: 1-22-99