


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Blitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Logan County. Sec. 4 Twp. 13 Rge. 36 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines Ne. NW. NE
Lease Owner Carl Lebsack et al.
Lease Name Settle Well No. 1
Office Address Hays, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 18 19 50
Application for plugging filed September 18 19 50
Application for plugging approved 19
Plugging commenced September 18 19 50
Plugging completed September 18 19 50
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well
Producing formation None Depth to top Bottom Total Depth of Well 4611 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10 3/4"	131'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug set at 130' with 1/2 sack of hulls and 20 sacks of cement filled hole to within 30' of cellar and cemented 2nd plug to bottom of cellar with 1/2 sack hulls and 15 sacks of cement.

09-21-50

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to
Address

STATE OF Kansas COUNTY OF Ellis, ss.
William R. Nye (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *William R. Nye*
(Address) 3 or 465 Hays

SUBSCRIBED AND SWORN TO before me this 20th day of September, 1950
Notary Public.

My commission expires 3/21/53
22-5188-a 9-48-10M
4 12 36
29 15

Company: Carl Lebsack et al
 Contractor: Glenn R. Nye Drilling Company
 Commenced: August 26, 1950
 Completed: September 18, 1950

Farm: Settle No. 1
 Location: NE NW NE 4 - 13 - 36
 Logan County, Kansas
 Casing Record: 10 3/4" set at 131'
 Elevation: 3012' D. F.

(Figures indicate bottoms)

surface soil & rock	40	lime & shale	3393	
sand & gravel	65	lime & shale	3412	
shale	70	lime & shale	3485	
sand & gravel	90	lime & shale	3540	
shale - blue	131	lime & shale	3600	
shale & clay	665	lime	3663	
lime shells & shale	750	lime	3705	
lime shells & shale	780	lime	3750	Top of
shale	1090	lime	3805	Heebner 3785'
shale & sand streaks	1150	lime	3834	Top K. C.
shale & shells	1200	lime	3887	Lansing 3835'
sandy lime	1245	lime	3913	
shale & shells & s.	1480	lime	3953	
shale, shells & pyrite iron	1630	lime	3987	
shale & shells	1690	lime	4020	
sand	1710	lime	4054	
red rock, shale & shells	1785	lime	4087	
anhydrite lime	1815	lime	4135	
red beds & shale	1835	lime hard	4175	
red beds & shale	2082	lime	4215	
anhydrite	2107	lime	4240	
red bed, shale & shells	2235	lime	4295	
shale, shells & red beds	2425	lime	4329	Top of
shale, shells & red bed	2575	lime	4358	Mississippi 4359'
shale, lime & red bed	2675	lime - cherty	4385	
shale, lime shells & red bed	2755	lime	4415	
shale, shells & red bed	2915	lime	4447	
shale, shells & lime	3020	lime	4459	
shale & lime	3025	lime	4470	
lime & shale	3035	lime	4505	
lime - dolomite	3050	lime - cherty	4531	
lime	3180	lime	4552	
lime	3205	lime	4568	
lime	3250	lime	4595	
lime	3280	lime	4605	
lime & shale	3350	Quartzite	4611	T. D.

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

GLENN R. NYE DRILLING COMPANY

By Glenn R. Nye

STATE of KANSAS)
) SS
 ELLIS COUNTY)

Subscribed to and sworn to before me, a notary public, in and for said County and State this 16 day of Sept, 1950.

Jan T. Shivers
 Notary Public

My Commission Expires. May 9, 1953

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 17 1950
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 4 T 13 R 36
 BOOK PAGE 29 LINE 15