

4-060864

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

4-2

API Number: 15-109-20,616-00-00

NE SE NE /4 SEC. 12, 13 S, 34 W
3630 feet from S section line
330 feet from E section line

Operator license# 5046

Lease: Holland Trust Well # 1

Operator: Raymond Oil Company

County: Logan

Address: P.O. Box 48788
Wichita, Kansas 67201

Well total depth 4580 ^{148.85} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 236 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Abercrombie Drilling Company, Inc. License# 5422

Address: Wichita, Kansas 67201

Company to plug at: Hour: P.M. Day: 2 Month: April Year: 1996

Plugging proposal received from: Tony

Company: Abercrombie Drilling Company, Inc. Phone: _____

Were: Order 190 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.
Space all plugs with heavy drilling mud through drill pipe.

04-12-96

KANSAS STATE COMMISSION
15th APR 12 A 11:18


Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 7:00 P.M., Day: 2, Month: April, Year: 1996

Actual plugging report:
1st. Plug at 2400' w/25 sxs.
2nd. Plug at 1360' w/100 sxs. - Anhydrite 2389' - 2411'.
3rd. Plug at 290' w/40 sxs. - Dakota 1059' - 1359'.
4th. Plug at 40' w/10 sxs. - Surface pipe to 236'.
15 sxs in rathole.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2959 GL

I did did not observe the plugging.


DH (agent)

INVOICED
DATE APR 22 1996
INV. NO. 45369
4-2