

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-109-20,581-0000

SW NW NW /4 SEC. 13 , 13 S, 34 W
4290 feet from S section line
4950 feet from E section line

Operator license# 31603 Lease Beckman well # 1

Operator: Adrian O. Miller County Logan 152.75

Address: P.O. Box 217 Well total depth 4700 feet
Wilson, Kansas 67490 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 264 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Oil Operations License# 8241

Address: _____

Company to plug at: Hour: A.M. Day: 11 Month: February Year: 95

Plugging proposal received from: Larry

Company: Emphasis Oil Operations Phone: _____

Were: Order 190 sxs. 60/40 pozmix - 10% gel - 3% c.c.
Allied Cement Company.
Condition hole with at least 36 vis. mud.

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 06 1995
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 10:00A.M., Day: 11, Month: February, Year: 95

Actual plugging report: Spot plugs with drill pipe.
1st. plug at 2400' w/25 sxs.
2nd. plug at 1450' w/100 sxs.
3rd. plug at 300' w/40 sxs.
4th. plug at 40' w/10 sxs. W.P.
8 5/8" set at 264' w/160 sxs. cwc.
Circulated 15 sxs. in rathole.

Remarks: Anhy. 2395'.

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: 2668 GL

I did NIV (did not) X observe the plugging. Carl Goodrow

HO (agent)

DATE 3-6-95
INV. NO. 42332