

11-19

4-090567

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API number: 15-109-20,661-00-00
80'S.&60'E.of
E2 W2 SW /4 SEC. 18, 13 S, 32 W
1240 feet from S section line
4230 feet from E section line

Operator license# 4729

Lease: Wieland Well # 1-18

Operator: Brito Oil Company, Inc.

County: Logan 154.70

Address: 120 S. Market - #400
Wichita, Kansas 67202

Well total depth 4760 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 3/4 Inch @ 220 feet

Aband. oil well _____, Gas well _____, Input well _____, SWD _____, D & A X

Plugging contractor: Abercrombie RTD, Inc. License# 30684

Address: Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 18 Month: November Year: 1997

Plugging proposal received from: Tony Martin

Company: Abercrombie RTD, Inc. Phone: -

Were: Order 190 sxs 60/40 pozmix - 6% gel.

Spot all plugs through drill pipe with heavy mud between all plugs.

11-25-97

Plugging Proposal Received by: Ed Schumacher

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 10:30 P.M., Day: 19, Month: November, Year: 1997

Actual plugging report: _____

1st. Plug at 2530' w/25 sxs cement.

2nd. Plug at 1485' w/100 sxs cement.

3rd. Plug at 270' w/40 sxs cement.

4th. Plug at 40' w/10 sxs cement.

15 sxs in rathole.

Anhydrite 2513' - Arbuckle - no.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES X NO _____

Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES X, NO _____

Plugged through TUBING _____, CASING _____ Elevation: 3035 GL

I did[] / did not[X] observe the plugging.

Ed Schumacher
(agent)

Form CP-2/3

INVOICED

DATE 12-3-97

INV. NO. 49587