

9-16

4-071068

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-109-20,438-00-01
NW SE NE /4 SEC. 18, 13 S, 32 W
1960 feet from S section line
700 feet from E section line

Operator license# 9860 Lease Voth (OWO) well # 1

Operator: Castle Resources, Inc. County Logan

Address: 1200 E. 27th Street Well total depth 2330 feet
Suite C Conductor Pipe: 0 inch @ 0 feet
Hays, Kansas 67601 Surface pipe 8 5/8 Inch @ 319 feet

75.72

Aband. oil well , Gas well , Input well , SWD , D & A X
(OWWO) wash down
Plugging contractor: Emphasis Oil Operations License#

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 16 Month: September Year: 93

Plugging proposal received from: Jack Fox

Company: Emphasis Oil Operations Phone: 913-625-5155

Were: 8 5/8" - 319' S.P. cwc. w/350 sxs. 60/40 pozmix - 6% gel. By
B.J. Titan. Elv. 3032' - Anhy. - 2506' - out of hole @ 2330'.
Proposal 190 sxs. 60/40 pozmix - 6% gel - 1 sx. hulls. Spot and displace
all cement through tubing. Heavy mud between al plugs - 25 sxs. cement
@ 2330' - 100 sxs. cement @ 1480' w/1 sx. flocele - 40 sxs. cement
@ 370' - 10 sxs. cement @ 40' - 15 sxs. in rathole. (circulate)

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 3:45P.M., Day: 16, Month: September, Year: 93

Actual plugging report: Emphasis ordered 190 sxs. 60/40 pozmix - 6% gel -
1 sx. flocele. Pumped in with pump truck - spotted and displaced all
cement through tubing. Heavy mud between all plugs.
1st. plug @ 2330' w/25 sxs. cement.
2nd. plug @ 1480' w/100 sxs. cement with 1 sxs. flocele.
3rd. plug @ 370' w/40 sxs. cement.
4th. plug @ 40' w/10 sxs. cement.
15 sxs. in rathole (circulate)

Remarks: By: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: GL

I did INVOICED did not X observe the plugging.

Marion J. Schmidt
(agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 13 1993
CONSERVATION DIVISION
Wichita, Kansas

DATE OCT 19 1993
INV. NO. 38962