

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20563-00-00
Spot: SWNESW Sec/Twnshp/Rge: 7-13S-33W
1650 feet from S Section Line, 1650 feet from W Section Line
Lease/Unit Name: LADENBERGER Well Number: 1
County: LOGAN Total Vertical Depth: 4610 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: PO BOX 352 370 W WICHITA AVE
RUSSELL, KS 67665

Conductor Pipe: Size feet: \$149.83
Surface Casing: Size 8.625 feet: 270 180 SXC MT
Production: Size 4.5 feet: 4597 225 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/23/2002 8:00 AM
Plug Co. License No.: 5135 Plug Co. Name: FARMER, JOHN O., INC.
Proposal Rcvd. from: VAL DREHER Company: FARMER, JOHN O., INC. Phone: (785) 483-8356

Proposed Plugging Method: Ordered out 260 sxs 60/40 pozmix - 10% gel.
Top down.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/23/2002 10:00 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" S.P. at 270' with 180 sxs.
Production casing 4 1/2" set at 4597' w/225 sxs.
Stage collar at 1873' cemented with 400 sxs.
Production perfs 4510' - 4514'; 4470' - 4490'. PBTD 4597'.
08-23-2002 - 4 1/2" production casing cemented with 500# hulls and 40 sxs 60/40 pozmix
- 10% gel and 16 sxs gel spacer and 95 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.
8 5/8" cemented with 10 sxs.
S.I.P. 200#.

ALLIED CEMENTING COMPANY
AUG 29 2002
08-29-2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Darrel Dipman PIRT 1
(TECHNICIAN)

INVOICED


DATE 9-4-02

NO. 2003060468

Form CP-2/3

AUG 26 2002

60 100 150 200 250 300 350 400 450 500 550 600 650 700 750 800 850 900 950 1000



replacement card

PRODUCTION DRILLING
HAYS KS 67601-0680

7-13S-33W
SW NE SW

1 LADENBERGER A

site: 1-1/4 N & 7-1/4 E OF RUSSELL SPRINGS KS	cty: LOGAN	API 15-109-20563									
contr: MURFIN DRILLING #3	field: LOGANSPO RT NW EXT (1/2	<table border="1"> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </table>									
geol: JOHN O FARMER IV	SW, INFLD DISC)										
fr date 02/04/94	spc date 04/19/94	orig comp 04/29/94									
		card issued 06/20/94									
		last revised 07/17/95									

ELV: 2976 KB, 2971 GL SMP
tops.....depth/datum
ANH.....2428 + 548
HEEB.....3847 - 871
LANS.....3893 - 917
FT SC.....4395 - 1419
JOHNSON ZN.....4468 - 1492
MISS.....4567 - 1591
PBTD.....4597 - 1621
RTD.....4610 - 1634
LOGGED

IP status:
 OIL, P 50 BO & 1 BWPD, CHER 4470-4514 OA, 05/24/94
 INFO REL: 7/17/95 - WAS OIL WELL - TIGHT HOLE
 NOTE: CORR 4/20/94 - ORIG FR AS # 1 LADENBERGER
 CSG: 8-5/8" 270 / 180 SX (ALT 2), 4-1/2" 4597 / 225 SX.
 MULTI STAGE COLLAR AT 1873 / 400 SX
 NO CORES
 DST (1) 3915-3971 (LANS B,C), / 45-45-60-60, REC 670'
 MW (REC CHL 60,000 PPM) ISIP 1226# FSIP 1216#
 IFP 49# -226# FFP 236# -324# IHP 1936# FHP 1886# BHT
 112'
 DST (2) 4445-4490 (JOHNSON ZN), HIT BRIDGE,
 MISRUN IHP 1086# FHP 1086# BHT 86'

COPYRIGHT 1995
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

(over)