

8-19

4-070107

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-109-20,,557-00-00
100'W of
NW NE NE ___/4 SEC. ___07___, ___13___ S, ___33___ W
4950 ___ feet from S section line
1090 ___ feet from E section line

Operator license# 5046

Lease: Ladenburgar Well # 1

Operator: Raymond Oil Company, Inc.

County: Logan 149.99

Address: P.O. Box 48788
Wichita, Kansas 67201

Well total depth 4615 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 232 feet

ABAND. oil well , Gas well ____, Input well ____, SWD. ____, D&A ____

Plugging contractor: Raymond Oil Company, Inc. License 5046

Address: P.O. Box 48788 - Wichita, Kansas 67201

Company to plug at: Hour: 10:30 A.M. Day: 19 Month: August Year: 1998

Plugging proposal received from: Art Schoenhofer

Company: Raymond Oil Company, Inc. Phone: 316-267-4214

Were: 4 1/2" set at 4604'. D.V. Tool 2389'.
8 5/8" set at 232'.
Ordered 185 sxs 60/40 pozmix - 10% gel with 500# hulls - 12 sxs gel.

RECEIVED
KANSAS CORPORATION COMMISSION

Plugging Proposal Received by: Rich Williams
Plugging operations attended by agent? All , Part [], None []

AUG 31 1998
08-31-1998

Completed: Hour: 2:15 P.M. Day: 19, Month: August, Year: 1998

CONSERVATION DIVISION
WICHITA KS

Actual plugging report: Allied pumped 30 sxs w/200# hulls, followed with 12 sxs gel with 250# hulls, followed with 100 sxs 60/40 pozmix - 10% gel. Max. P.S.I. 1500#. S.I.P. 1200#. Hooked-up to backside and pumped 10 sxs with 50# hulls. Max. P.S.I. 500#. S.I.P. 500#.

Remarks: Condition of casing(in hole): GOOD BAD ___ Anhy.plug: YES NO ___
Bottom plug(in place): YES , CALC ____, NO ___ Dakota plug: YES , NO ___
Plugged through TUBING ____, CASING . Elevation: 3009 GL

I did / did not [] observe the plugging.

Richard Williams
(agent)

Form CP-2/3

INVOICED

DATE 9-2-98

INV. NO. 51242

8-19