

020524

1-6

28612

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-199-20184-00-00 199-20,184

NW NW NW SEC. 31 T 13 S, R 42 W/XXX

4950 feet from S section line

5000 feet from E section line

TECHNICIAN'S PLUGGING REPORT

6417

Operator License # _____

Lease Name Eagle Margerite Well # 1 (11-31)

Operator: Union Pacific Resources Company

County Wallace 174.53

Name & Address: Box 7 MS 3407

Well Total Depth 5370 feet

Fort Worth, Texas 76101-0007

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet set at 617

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rains And Williamson License Number 5146

Address _____

Company to plug at: Hour: _____ PM Day: 6 Month: Jan Year: 19 90

Plugging proposal received from _____

(company name) _____ (phone) _____

were: Order 190 sks 60/40 poz 6% gel 1/2 flocele/celoflake.

Plugging Proposal Received by Gilbert Balthazor (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:00AM Day: 6 Month: Jan Year: 19 90

ACTUAL PLUGGING REPORT Spot through drill pipe w/heavy mud between all plugs.

1st plug at 2940' w/25 sks

2nd plug at 2080' w/100 sks

3rd plug at 620' w/40 sks

4th plug at 40' w/10 sks w/wiper
15 sks in rathole 10 sks in mousehole.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED (No) Observe this plugging.

DATE FEB 08 1990

INV. NO. 27367

Signed: Gilbert Balthazor (TECHNICIAN)

STATE RECEIVED

JAN 26 1990

COM. DIVISION 01-26-90