

6010174

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-199-20054-00-00

SW, SEC. 9, T. 13 S, R. 38 W/D  
1280 feet from N/S section line

2310 feet from W/D section line

Lease Name Sidebottom Well # 1

County Wallace

Well Total Depth 4900 <sup>159.25</sup> feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 516

TECHNICIAN'S PLUGGING REPORT

Operator License # 5469

Operator: Anadarko prod. Co.

Name & Address Box 351

Liberal Ks.

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well (D&A)

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor SLAWSON License Number 5181

Address Wichita Ks.

Company to plug at: Hour: 11:30 PM Day: 19 Month: 7 Year: 19 84

Plugging proposal received from Jim Barlow

(company name) Anadarko <sup>316</sup> (phone) 624-6253

were: order 185 sx cement 50/50 pozmix 6% gel. 3% c.c.

1 sx hulls 1-8 5/8 plug 1 sx Flow Seal

Heavy mud between all plugs.

Pump cem. down drill pipe.

Elev. 3245 Anhydrite. 2545-79 Arbuckle. No

Dakota 1950 Plugging Proposal Received by Dale Batthazor

1295 = 1600

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ (None)

Operations Completed: Hour: 8:30 AM Day: 20 Month: 7 Year: 19 84

ACTUAL PLUGGING REPORT Hit a solid bridge @ 2263 circled

for 20 mi. could not get deeper.

25 sx @ 2263

100 sx @ 1745 mixed with 1 sx Flowseal.

40 sx @ 550 dumped 1 sx hulls pushed plug to 40'

10 sx @ 40 (Temp. lost circ @ 1242) Mike Larson

Remarks: 10 sx in Rat Hole cementing Co. SUN.

(If additional description is necessary, use BACK of this form.)

INVOICED (circled) observe + STATE CORPORATION COMMISSION

DATE 7-31-84

JUL 30 1984  
07-30-1984

Signed Dale Batthazor  
(TECHNICIAN)

INV. NO. 2794 AUG 21 1984

CONSERVATION DIVISION  
Wichita, Kansas

Handwritten initials and number 26/3