

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-199-20, 071-00-00
660 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5476
Operator: DNB DRILLING, INC
Name & Address: 535 N OLIVER
WICHITA, KANS. 67208
JAMES DONELSON, JR.

Lease Name BIEMER Well # 1
County WALLACE 160.88
Well Total Depth 4950 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 458

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor CHEYENNE DRILLING INC License Number 5282
Address GARDEN CITY KANS.

Company to plug at: Hour: 8:00 AM Day: 2 ND Month: DEC. Year: 19 85

Plugging proposal received from RON OSTERBUHR.

(company name) DNB DRILLING, INC. (phone) 316-681-5471

were: 8 5/8 - 458 FT SR CUM 1/175 CMT, CEMENTED BY HALLIBURTON CMT.
ORDER 215 SK 60/40 TORMIX GEL - CA-CL - 1 SK FLANK BY HALLIBURTON, CMT.
SPT WITH DRILL STEM, RECONDITION WOLE (VISCOSITY) HEAVY MUD BETWEEN PLUGS.
NO PARACHIE, ELV. 3355, ANHY. 2580, NO CIRCULATION PROBLEMS,
MUD CONDUCTION. VISCOSITY 50, WEIGHT 9.2,

Plugging Proposal Received by Maurice Schmidt
DOBIC (TECHNICIAN)

Plugging Operations attended by Agent: All _____ Part _____ None X

Operations Completed: Hour: 8:00 AM Day: 2 ND Month: DEC Year: 19 85

ACTUAL PLUGGING REPORT ORDERED 215 SK 60/40 TORMIX GEL - CA-CL - AND 8 5/8" PLUG

SPOTTED WITH DRILL STEM, RECONDITIONED WOLE, HEAVY MUD BETWEEN PLUGS
1 ST PLUG @ 2600 FT 1/30 SK CMT, 2 ND PLUG @ 1600 FT 1/100 CMT 1/4 SK CERO
3 RD PLUG @ 375 FT 1/50 SK CMT, 4 TH PLUG SOLID BRIDGE HULLS - PLUG @ 40' TO 0 1/10 SK CMT.
15 SK IN RAT HOLE (CIRCULATE), 10 SK IN MOUSE HOLE (CIRCULATE)
CEMENTED BY HALLIBURTON CMT

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 16 1985
INV. NO. 11519
12-2

STATE CORPORATION COMMISSION
12-09-1985
DEC 3 1985

Signed Maurice Schmidt
DOBIC (TECHNICIAN)
4 12-6-85
MPB

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 11 - 15 - 85
month day year

API Number 15- 199-20,071-00-00

OPERATOR: License # 5476
Name DNB Drilling, Inc.
Address 535 N. Oliver
City/State/Zip Wichita, KS 67208
Contact Person James Donelson, Jr.
Phone (316) 687-5471

C SW SE Sec. 9, Twp. 13, S. Rge. 39. East West
(location)
660 Ft North from Southeast Corner of Section
1980 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5382
Name Cheyenne Drilling, Inc.
City/State Garden City, KS

Nearest lease or unit boundary line ... 660. feet.
County Wallace
Lease Name Bieker Well# 1
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water 150 feet
Lowest usable water formation Dakota
Depth to Bottom of usable water 1700 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 350 (358) feet
Conductor pipe if any required feet
Ground surface elevation 3345 - est. feet MSL.
This Authorization Expires 5-5-86
Approved By 11-5-85 [Signature]

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 4950 feet
Projected Formation at TD Mississippi
Expected Producing Formations Mississippi

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 11-4-85 Signature of Operator or Agent [Signature] Title General Manager

Form C-1 4/84

spud 10:PM 11-23-85

Phil Loyd Cheyenne Drilling, Howling, Wale

RECEIVED
STATE CORPORATION COMMISSION
12-09-1985
DEC 9 1985

RECEIVED
KCC-KDHE
NOV 18 1985
JOINT DIST #6
HAYS, KS

CONSERVATION DIVISION
Wichita, Kansas