

X 11-2

6 070723

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C NW SE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 199-20,166-00-00
SEC. 20, T 13 S, R 39
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5806

Lease Name Dale Radiel Well # 1
County Wallace 156.00
Well Total Depth 4800 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 310

Operator: Erbert Oil, Harold
Name & Address 2904 North State
Iola, Ks. 66749

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well _____ U&A
Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil License Number 8241
Address Russell, Ks. 67665

Company to plug at: Hour: AM Day: 2 Month: Nov Year: 19 88

Plugging proposal received from Tom Alm

(company name) Emphasis Oil (phone) _____

were: 8 5/8" 310' S.P. cwc w/175 sks 60/40 Poz 2% Gel 3% Cal Cl (By Allied)

No Arbuckle. Elv. 3394'. Anhy 2618'. No circulation problems.
Mud condition 50 vis. 9# weight; 8 water loss. Proposal 225 sks 60/40 Poz 6% Gel 2% Cal Cl,
and 8 5/8" plug; Spot with drill stem, circulate, heavy mud between all plugs. 40 sks
at 2600'; 100 sks at 1640'; 50 sks at 360'; 10 sks at 40'; 15 sks rathole (cir) 10 sks

mousehole (cir) Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 9:30AM Day: 2 Month: Nov Year: 19 88

ACTUAL PLUGGING REPORT Ordered 225 sks 60/40 Poz 6% Gel 3% Cal Cl and 8 5/8" plug.

Spotted with drill stem, circulated hole, mud between all plugs. 1st plug at 2600' w/40 sks
cement; 2nd plug at 1640' w/100 sks cement w/1 sk Flocele. 3rd plug at 360' w/50 sks cement;

4th plug Hulls - Plug at 40' w/10 sks cement in rathole (cir) 10 sks in mousehole
(circulate).

RECEIVED
STATE CORPORATION COMMISSION

NOV 21 1988
11-21-1988
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Cemented by Allied Cement
(If additional description is necessary, use BACK of this form.)

INVOICED
I did not observe this plugging.

DATE 11-29-88

Signed Marion J. Schmidt
(TECHNICIAN)
Marion J. Schmidt

INV. NO. 23137