

15-115-19237-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



NORTH



Locate well correctly on above
Section Plat

Marion County. Sec. 23 Twp. 17S Rge. 4 (E) X (W)
Location as "NE/CNWSW" or footage from lines SE SE SW
Lease Owner Murfin Drilling Company
Lease Name SKLENAR Well No. Two
Office Address 617 Union Center Building - Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 1/3/57 19
Application for plugging filed 2/9/62 19
Application for plugging approved 2/9/62 19
Plugging commenced 2/9/62 19
Plugging completed 2/13/62 19
Reason for abandonment of well or producing formation Well Not producing
in commercial quantities
If a producing well is abandoned, date of last production February 8 19 62
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Cecil M. Jones - 1114 N. Walnut - McPherson, Ks.
Producing formation Mississippi Chat Depth to top 2347' Bottom 2348' Total Depth of Well 2351' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	225'	None
				4 1/2"	2348'	2013'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand 2351' to 2340', 4 sacks cement @ 2340', Mud 2340' to 220', Rock 220' to 200', 3 yards ready-mix cement to surface.

APR 11 1962
04-05-62
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Murfin Drilling Company
Address 617 Union Center Bldg. - Wichita 2, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.
Fred Murfin - Partner (employer of owner) and owner of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Fred Murfin*
617 Union Center Building - Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of April, 19 62

Mary Paula Blume
Notary Public.

My commission expires June 14, 1964

WELL LOG

15-115-19237-0000
P

COMPANY **Murfin Drilling Company**
FARM **SKLENAR** NO. **Two**

SEC. **23** T. **17s** R. **4E**
LOC. **SE SE SW**

TOTAL DEPTH **2351'**
COMM. **12/30/56** COMP. **1/3/57**
SHOT OR TREATED **No**
CONTRACTOR **Sunflower Drilling Company**
ISSUED

COUNTRY **Marion**
KANSAS



CASING
20 10
15 8 **5/8" 225' with 200 sacks cement**
12 6
13 5
4 1/2" 2348' with 50 sacks cement

ELEVATION **1469' KB**
PRODUCTION **Oil**

FIGURES INDICATE BOTTOM OF FORMATIONS

- 10' Soil & Clay
- 35' Shale
- 165' Shale & Shells
- 185' Red Bed
- 290' Lime & Shale
- 300' Lime
- 335' Lime & Shale
- 385' Lime
- 400' Shale
- 405' Lime
- 745' Lime & Shale
- 850' Shale & Shells
- 1005' Shale
- 1085' Lime & Shale
- 1190' Shale & Shells
- 1210' Lime
- 1270' Shale
- 1325' Lime & Shale
- 1375' Shale & Shells
- 1480' Lime & Shale
- 1635' Lime
- 1710' Shale & Shells
- 1735' Lime & Shale
- 1755' Shale
- 1809' Lime & Shale
- 2150' Lime K. C.
- 2348' Shale & Shells
- 2351' Chat Miss.

RECEIVED
STATE COMPTROLLER COMMISSION
APR 5 1962
CONSERVATION DIVISION
Topeka, Kansas

State of Kansas
County of Sedgewick ss:

I, Fred Murfin - Partner of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the SKLENAR #2 well.

Subscribed and sworn to before me this 4th day of April 19 62

My Commission Expires: June 14, 1964

Mary Ann Blume
NOTARY PUBLIC