

15-199-20034-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Wallace County, Sec. 6 Twp. 13S Rge. 39 xxxw
Location as "NE/CNW SW 1/4" or footage from lines SW NE

Lease Owner Burnett Corporation
Lease Name Scheetz Well No. 1
Office Address 328 1st Natl Bk Bldg, Amarillo, Tx 79101


Character of Well (Completed as Oil, Gas or Dry Hole) dry hole

Date Well completed 8-8-79
Application for plugging filed 8-8-79
Application for plugging approved 8-8-79
Plugging commenced 8-8-79
Plugging completed 8-8-79

Reason for abandonment of well or producing formation no commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2700
Show depth and thickness of all water, oil and gas formations.



OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|--------------|---------|------|------|-------|--------|------------|
| surface hole | shale | surf | 640' | 8-5/8 | 631 | none |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- Fluid to 1515', plug, 60 sx
- Fluid to 630', plug, 30 sx
- Fluid to 40', plug, 10 sx
- Rat hole 5 sx

RECEIVED
STATE CORPORATION COMMISSION
08-30-1979
AUG 30 1979
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor DNB DRILLING, INC.
515 R. H. Garvey Bldg
Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Ella Priess (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ella Priess
515 R.H. Garvey Bldg., Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of August, 19 79

Dorothy L. Schmidt
Dorothy L. Schmidt Notary Public.

My commission expires April 30, 1983

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1983

15-199-20034-00-00

DRILLER'S LOG

BURNETT CORPORATION
No. 1 Scheetz
SW NE Sec 6-13S-39W
Wallace Co., Ks.

Commenced: 8-4-79
Completed: 8-8-79

Surface Casing: 631' of 8-5/8"
cemented w/400 sx Class H cement
3% cc, 1/4# Floseal

FORMATION

DEPTH

| | |
|--------------|-----------------|
| Surface Hole | 0 - 640 |
| Sand & Shale | 640 - 1480 |
| Shale | 1480 - 2265 |
| Shale & Sand | 2265 - 2650 |
| Anhydrite | 2650 - 2681 |
| Shale | 2681 - 2700 RTD |

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

Ella Priess

Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 9th day of August, 1979.

Dorothy L. Schmidt

Dorothy L. Schmidt, Notary Public

RECEIVED DOROTHY L. SCHMIDT
STATE CORPORATION COMMISSION STATE NOTARY PUBLIC
Sedwick, Kansas

AUG 30 1979
08-30-1979
CONSERVATION DIVISION
Wichita, Kansas