

WELL PLUGGING RECORD

15-199-20016-00-00

Give All Information Completely
 Make Required Affidavit

COUNTY Wallace SEC. 17 TWP. 13S RGE. 39W E/W
 Location as in quarters or footage from lines:
C NE NE

			①

Locate Well
 correctly on above
 Section Platt.

Lease Owner Burnett Corporation
 Lease Name Pancake Well No. 1
 Office Address Box 1873 Liberal, Kansas 67901
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed 8-11-81
 Application for plugging filed 8-7-81
 Plugging commenced 8-14-81
 Plugging completed 8-17-81
 Reason for abandonment of well or producing formation
Formation Making 100% Water Could not Squeeze off
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
 Producing formation Upper Morrow Depth to top 4652' bottom 4660' T.D. 4850
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	331	none
				4 1/2	4793	3232

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pump 20 sks. of cement to 4420
 Pump 5 sks. of hull's & 2 sks. of mud w/ 60 sks. of cement @ 1400
 Pump 1 sk. of hull's & 1 sk. of mud w/ 30 sks. of cement @ 300
 Put 10 sks. of cement from 40 to 4

Cut off & cap 8 5/8 3' below ground level

RECEIVED

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent's Casing Pulling Ser.
Box 506 Liberal, Kansas 67901

1981
 09-11-1981

STATE OF KANSAS COUNTY OF SEWARD, ss.

EMPLOYEE OF OWNER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) A. L. Chiles
PO Box 1873
 Liberal Kansas 67901

SUBSCRIBED AND SWORN TO before me this 8th day of Sept, 19 81

Virginia Buehler
 Notary Public.

My Commission expires: 7/14/84

DRILLERS' LOG



K. G. S. LIBRARY

BURNETT CORPORATION
No. 1 Pancake
C NE NE Sec. 17-13S-39W
Wallace County, Kansas

Commenced: 7-9-77
Completed: 7-19-77

Surface Casing: 324' of 8-5/8"
cemented with 275 sx Class H, 3% cc
7-9-77

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 331
Shale	331 - 625
Sand & Shale	625 - 1915
Shale	1915 - 3144
Shale, Salt Straks & Sand	3144 - 3385
Lime & Shale	3385 - 4135
Lime	4135 - 4565
Lime & Shale	4565 - 4701
Lime	4701 - 4850 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

Ella Priess


Ella Priess

9-26-77

STATE OF KANSAS

Subscribed and

BURNETT CORP.
SUITE 450 1ST NATL. BANK BLDG. #1 PANCAKE 17-13-39W
AMARILLO, TX. C NE NE
CONTR DNB DRG., INC. CTY WALLACE
GEOLOG CLIFF VAUGHAN FIELD SHARON SPRINGS CONF
E 3376 KB CM 7/9/77 CARD ISSUED 9/22/77 IP P 90 BOPD + 40 BWP
MRW 4652-60



API 15-199-20,015

LOG	TOPS	DEPTH	DATUM
B ANH	2599	+ 777	
NEVA	3168	+ 208	
HEER	3868	- 492	
TOR	3893	- 517	
LKC	3918	- 542	
MARM	4301	- 925	
CHER	4431	-1055	
MRW	4631	-1255	
MISS (STE GEN)	4766	-1390	
LTD	4843	-1467	
RTD	4850	-1474	

8-5/8" 331/275sx, 4 1/2" 4838/200sx
DST (1) 4612-4658 (U MRW)/30-60-290-
120, 1200' SMCGO, SIP 1061-1051#
FP 37-130#, 149-521#
MICT - PF 4652-60, AC 1500, SWB LD,
SWB 7.14 BOPH/10 HRS, GR 39°, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION

AUG 12 1981
08-12-1981
CONSERVATION DIVISION
Wichita, Kansas