

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-051-21,953-00-00

LEASE NAME Furthmyer

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

4950 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 28 TWP. 14 RGE. 16 (X) or (W)

COUNTY Ellis

LEASE OPERATOR D Oil, Inc.

ADDRESS P. O. Box 278

PHONE#(913) 735 9225 OPERATORS LICENSE NO. 9394

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 4-9-80

Plugging Commenced 10-29-90

Plugging Completed 10-29-90

The plugging proposal was approved on 10-4-90 (date)

by Gib Scheck (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top 3400 Bottom 3415 T.D. 3415

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface		0	217	8 5/8	213	0
Production		0	3410	4 1/2	3410	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped in 25 sks. 65-35 Poz cement, follow with 175 sks. 65-35 Poz and 500# hulls with 1000# PSI. Tied into surface pipe at 400# PSI.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B.J. Titan Services (Hays Dist.) License No. \_\_\_\_\_

Address P.O. Box 4442 Houston, Tx.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: D Oil, Inc. 11-02-1990

STATE OF Kansas COUNTY OF ellis ss. \_\_\_\_\_

Alfred J. Dreiling

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. 278 Victoria, Ks. 67671

SUBSCRIBED AND SWORN TO before me this 1st. day of November, 1990



Sheila Kuhn  
Notary Public

15-051-21953-00-00

DRILLERS' WELL LOG

DATE COMMENCED: April 3, 1980  
DATE COMPLETED: April 9, 1980

D Oil Operations  
FURTHMYER #1  
NE NE NW  
Sec. 23-T14S-R16 W  
Ellis County, Kansas

0 - 218' Surface Clay, Post Rock  
218 - 978' Shale, Sand, Redbed  
978 - 1025' Anhydrite  
1025 - 2810' Shale & Lime  
2810 - 2851' Lime  
2851 - 2865' Shale  
2865 - 3088' Lime  
3088 - 3092' Shale  
3092 - 3110' Lime & Shale  
3110 - 3122' Lime  
3122 - 3140' Shale  
3140 - 3368' Lime  
3368 - 3405' Shale & Lime  
3405 - 3415' Dolomite  
3415' RTD

ELEVATION: 1880 K.B.

FORMATION DATA

ANHYDRITE 978'  
HOWARD 2810  
SEVERY 2851  
TOPEKA 2865  
HEEBNER 3088  
TORONTO 3110  
DOUGLAS 3122  
KANSAS CITY 3140  
BASE K.C. 3368  
ARBUCKLE 3405  
RTD 3415

SURFACE PIPE: Set used 28#,  
8-5/8" pipe at 217' w/140 sacks 60/40  
pozmix, 2% Gel, 3% cc.

PRODUCTION PIPE: Set new 4 1/2",  
9 1/2# pipe at 3405' w/150 sacks  
60/40 pozmix, 10% Salt, run a  
DV tool 1026' cemented w/300  
sacks 50/50 pozmix, 5% gel.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON ) ss

Leonard Williamson, of lawful age does swear and state that the facts  
and statements herein contained are true and correct to the best of his knowledge.

*Leonard Williamson*

Subscribed and sworn to before me this 17 day of April 1980

My Comm. Expires:  
4-11-1982

*Dorothy M. Hague*

STATE COMPTROLLER COMMISSIONER

OCT 4 1980  
10-04-1980  
Wichita, Kansas