


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ellis

County, Sec. 28 Twp. 14 Rge. 16 (E) V (W)

Location as "NE/CNW/SE" or footage from lines NE¹/₄ NE¹/₄ NE¹/₄

Lease Owner Courtney B. Davis

Lease Name Davis - Dinkel No 1 Well No. _____

Office Address Wichita, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed _____ 19__

Application for plugging approved _____ 19__

Plugging commenced June 8 19 55

Plugging completed July 8 19 55

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes.

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3390 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3390 feet to surface feet for each plug set.

Hole filled with sand from 3390 to 3350; four sacks of cement placed with dump bailer to form plug between 3350 to 3318; Halliburton pump trucks pumped in 30 sacks of mud and 80 sacks of cement after pipe had been pulled to cement well to surface.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes and Sons Pipe Pulling Co

Address Russell Kansas.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Courtney B. Davis (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Courtney B. Davis
402-Van N. Bank Bldg. Wichita-Kan. (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of August, 19 55

My commission expires July 16, 1957

Walter A. Stansbury Notary Public.

PLUGGING
FILE SEC 28 T 14 R 16 W
BOOK PAGE 133 LINE 16

08-30-1955

15-051-05154-00-00

OPERATOR: Courtney B. David, Inc.
402 Union Nat'l. Bank Bldg.
Wichita, Kansas

CONTRACTOR: MAST DRILLING, INC.
Russell, Kansas

LEASE: Pinhol #1
NE/4 NE/4 NE/4
Section 28-14-16 W
Ellis County, Ks.

COMMENCED: 12-1-54

COMPLETED: 12-10-54

FORMATION

DEPTH

Shale & Shells	480
Sand	575
Red Bed & Shale	900
Anhydrite	992
Shale & Red Rock	1225
Shale-Shells-Salt	1805
Lime & Shale	2080
Lime	2140
Lime & Shale	2300
Shale-Shells	2350
Lime & Shale	2450
Shale	2630
Shale & Lime	2876
Shale	2845
Lime	3055
Shale	3080
Lime	3370
Arbuckle	3390
TOTAL DEPTH	3390

I hereby certify that the above is true and correct to the best of my knowledge.

Mast Drilling, Inc.

James J. Thomas

STATE OF KANSAS)
)ss
COUNTY OF RUSSELL)

Subscribed and sworn to before me this 4th day of June, 1955.

Betty Jean Talbot
Notary Public

My Commission expires 8-9-58

PLUGGING
FILE SEC 28 T 14 R 16 W
BOOK PAGE 133 LINE 16

RECEIVED
KANSAS CONSERVATION COMMISSION
AUG 27 1955
08-30-1955
CONSERVATION DIVISION
Wichita, Kansas