

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-051, 24, 328-00-00

LEASE NAME Baumrucker

WELL NUMBER #"B" #1

2970 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 25 TWP. 14 RGE. 16 (E) or (W)

COUNTY Ellis

Date Well Completed \_\_\_\_\_

Plugging Commenced 4-24-89

Plugging Completed 4-27-89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Oil Producers, Inc. of Kansas

ADDRESS Box 8647, Wichita, Kansas 67202

PHONE 316-672-3440 OPERATORS LICENSE NO. 8061

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which agent did you notify? Gilbert Scheck

Is ACO-1 filed? Yes If 9-9-89 well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3365'

Show depth and thickness of water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	907'	None
				4-1/2"	3362'	2,566.28'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet, each set. Dumped sand to 3250' and 4 sacks cement. Shot casing at 2800 and 2500'. Pulled 75 joints of 4-1/2" casing. Howco plugged well with 5 sacks hulls and 200 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 750 psi and shutin 400 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530


STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold  
(Address) James W. Rockhold  
Box 698, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 8th day of May, 1989

My Commission Expires \_\_\_\_\_



Notary Public