

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-169-00251-00-00

API NUMBER 12-3-63

LEASE NAME Gilmore

WELL NUMBER #1

3630 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 17 TWP. 14S RGE. 2 (E) or (W)

COUNTY Saline

Date Well Completed 12-3-63

Plugging Commenced 5-6-88

Plugging Completed 5-10-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Scott's Well Service

ADDRESS Box 36 Roxbury, Ks 67476

PHONE# (913) 254 7828 OPERATORS LICENSE NO. 6819

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 21, 1988

by Shari Feist (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Maquoketa Depth to Top 3113 Bottom 3017

Show depth and thickness of all water, oil and gas formations.

RECEIVED (date)
STATE CORPORATION COMMISSION
MAY 17 1988
CONSERVATION DIVISION
Wichita, Kansas

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Maquoketa	dolomite	surface	3198	4"	3198	1550'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sanded from bottom of well to 3100' and capped with 4 sacks cement. Recovered 1550' of pipe. Solid bridge at 300' filled redi mix to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Scott's Well Service License No. 6819

Address Box 36, Roxbury, Ks 67476

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Scott's Well Service

STATE OF Kansas COUNTY OF McPherson, ss.

Jay Scott (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jay Scott

(Address) Box 36, Roxbury, Ks 67476

SUBSCRIBED AND SWORN TO before me this 16 day of May, 19 88

Carol Decker
Notary Public

My Commission Expires: August 15, 1991



15-169-0025100-00


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **WALTER J. NELSON, ET AL**
Farm- **Gillmore** No. **1**

SEC. 16 T. 14 R. 2W
C SW NW

Total Depth. **3204'**
Comm. **12-19-62** Comp. **12-31-62**
Shot or Treated.
Contractor. **Donald T. Ingling**
Issued. **4-13-63**

County **Saline**
KANSAS



Elevation. **1253' RB**

Production. **30 BOPD & 5% WTR.**

CASING:

8 5/8" 215' cem w/150 sx.
4 1/2" 3201 3/4' cem w/75 sx.

Figures indicate Bottom of Formations.

shale & sand	70
lime & shale	120
lime	215
lime & shale	430
lime & sandy lime	560
lime	780
shale	1080
shale & lime streaks	1383
shale & shells	1585
lime & shale	1760
shale & lime	1975
lime	2040
lime & shale	2170
shale & lime	2223
lime	2340
shale & lime	2380
lime	2470
lime & shale	2530
shale & lime	2625
chat & lime	2694
Mississippi	2760
lime	2890
shale	3010
lime & sand	3060
lime	3112
lime & shale	3115
shale	3125
shale - Maquoketa	3201
dolomite - Maquoketa	3204 RTD
Total Depth	
TOPS: SAMPLE	
Mississippi	2635
Kinderhook	2871
Hunton	3002
Maquoketa	3201

RECEIVED
STATE CORPORATION COMMISSION

FEB 21 1974

CONSERVATION DIVISION
Wichita, Kansas

02-21-1974