

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-051-21314-00-00

LEASE NAME Younger

WELL NUMBER #5

SPOT LOCATION NE SW NW

SEC. 25 TWP. 13 RGE. 20 (X) or (W)

COUNTY Ellis

Date Well Completed 5-16-77

Plugging Commenced 8-11-86

Plugging Completed 8-11-86

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Liberty Operations and Completions, Inc.

ADDRESS 308 West Mill, Plainville, Kansas 67663

PHONE # (913) 434-4686 OPERATORS LICENSE NO. 8925

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas Office

Is ACO-1 filed? no If not, is well log attached? It was sent in with application

Producing formation Lansing/KC Depth to top 3420 bottom 3448 T.D. 3497

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing	Oil	3420	3448	5 1/2	3497	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pulled all tubing out of well. Did not pull any casing, holes in casing around 700. Allied cemented inside casing with 125 sacks A.T.L. maximum pressure 400#, shut in 200#. Didn't circulate. Pumped 100 sacks cement with 4 sacks cottonseed hulls down annulus. Pressured up to 500#, shut-in 200#.


(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Liberty Operations and Completions, Inc. License No. 8925  
Address 308 West Mill, Plainville, Kansas 67663

STATE OF Kansas COUNTY OF Rooks, ss.

Richard Williams (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Richard Williams  
Richard Williams  
(Address) 308 West Mill, Plainville, KS 67663



SUBSCRIBED AND SWORN TO before me this 13<sup>th</sup> day of August, 1986

Jolene Garvert  
Notary Public  
Jolene Garvert

My Commission expires: 3-9-88 08-14-86

AUG 14

