

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33097
Name: Southern Star Central Gas Pipeline
Address 1: 4700 Hwy 56 P.O. Box 20010
Address 2: _____
City: Owensboro State: KY Zip: 42301 + _____
Contact Person: Mark Rouse
Phone: (270) 852-4490
Type of Well: (Check one) ☒ Oil Well ☐ Gas Well ☐ OG ☐ D&A ☐ Cathodic
☐ Water Supply Well ☐ Other: _____ ☐ SWD Permit #: _____
☐ ENHR Permit #: _____ ☐ Gas Storage Permit #: _____
Is ACO-1 filed? ☐ Yes ☐ No If not, is well log attached? ☐ Yes ☒ No
Producing Formation(s): List All (If needed attach another sheet)
Squirrel Depth to Top: 823' Bottom: 826.5' T.D. 849'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 003-22032-00-00
Spot Description: _____
NW - NW SE SW Sec. 16 Twp 22 S. R. 19 ☒ East ☐ West
1100' Feet from ☐ North / ☒ South Line of Section
3740 3711 Feet from ☒ East / ☐ West Line of Section
Footages Calculated from Nearest Outside Section Corner:
☐ NE ☐ NW ☐ SE ☐ SW
County: Anderson
Lease Name: Boots Well #: 7-New #03
Date Well Completed: 8-23-82
The plugging proposal was approved on: 6-30-10 (Date)
by: Steve Bond (KCC District Agent's Name)
Plugging Commenced: 10-06-10
Plugging Completed: 10-06-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		<u>Surface</u>	<u>6 1/4"</u>	<u>48.6'</u>	
<u>Squirrel</u>		<u>Production</u>	<u>2 1/2"</u>	<u>849'</u>	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rig up to 1" pipe, washed down and circulated well clean. Mixed cement until good returns.
Pulled 1" pipe. Filled tubing with cement. Rigged up to tubing. Mixed cement along with Halls
and squeezed into formation at 150 psi and shutting in at 700 psi. 63 sacks of
cement used on well for plugging.

Plugging Contractor License #: 34059 Name: Hurricane Services, INC
Address 1: P.O. Box 782228 Address 2: _____
City: Wichita State: Kansas Zip: 67278-2228
Phone: (316) 685-5908
Name of Party Responsible for Plugging Fees: Southern Star
State of Kentucky County: Davis ss. _____
Sterling Barker ☒ Employee of Operator or ☐ Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Sterling Barker

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

NOV 24 2010

KCC WICHITA