

KCC COPY

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 34103 Name: Lamamco Drilling Company Address 1: P.O. Box 550 Address 2: City: Skiatook State: OK Zip: 74070 Contact Person: Thomas H. Oast Phone: (620) 725-3200 Type of Well: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (if needed attach another sheet) Wayside SS Depth to Top: 925' Bottom: 943' T.D. 987'

API No. 15 - 019-20,882-0002 Spot Description: C NE SW NW Sec. 27 Twp. 33 S. R. 12 East West 3,630 Feet from North South Line of Section 4,290 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Chautauqua Lease Name: Raymon E Well #: 6 Date Well Completed: 8/26/1977 The plugging proposal was approved on: May 19, 2010 (Date) by: Duane Sims (KCC District Agent's Name) Plugging Commenced: June 16, 2010 Plugging Completed: June 16, 2010

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Rows include Wayside Sandstone with Oil content and Surface/Production casing records.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 1" tubing to 956'. Gel hole with 2 sacks. Spot 10 sacks Portland Type 1 at bottom. Pull 1" tubing up to 700' and spot an additional 5 sacks cement. Pull 1" tubing up to 350' and cement to surface. Finish pulling tubing from well and top off with cement. Restore location. INVOICE NUMBER 8669 dated 6-16-2010

RECEIVED KANSAS CORPORATION COMMISSION

JUN 25 2010

CONSERVATION DIVISION WICHITA, KS

Plugging Contractor License #: 32884 Name: Elmore's Inc. Address 1: Box 87 Address 2: 776 Highway 99 City: Sedan State: Kansas Zip: 67361 Phone: (620) 249-2519 Name of Party Responsible for Plugging Fees: Lamamco Drilling Company - Blain Haag State of Kansas County: Chautauqua, ss. Thomas H. Oast Employee of Operator or Operator on above-described well

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Handwritten Signature]

[Handwritten mark]

**STATEMENT**

8669

**ELMORE'S INC.**  
 Box 87 - 776 HWY99  
 Sedan, KS 67361  
 Cell: (620) 249-2519  
 Eve: (620) 725-5538

Date 6-16-10

Customer Lamanco  
 Address \_\_\_\_\_  
 City \_\_\_\_\_ State \_\_\_\_\_ Zip \_\_\_\_\_

Qty.	Description	Price	Amount
4 1/2 hr	Pulling	95.00	427.50
3 hr	Cement Pump	100.00	300.00
3 hr	Vac Truck	80.00	240.00
1	Rawlck Tank	80.00	80.00
50	Sks Cement	7.95	397.50
2	Sks Gel	15.00	30.00
350'	1" Tubin Rental	.10	35.00
			1510.00
	Plug Job Raymond - 6 Tax		95.13
	Ran 1" To 956 Gel Hole		1605.13
	With 2 Sks Gel Spotted 10		
	Sks Cement on Bottom Pulled		
	1" Hoto 200' Spotted 5 Sks Cement		
	Pulled 1" Hoto 350' Cemented To		
	Surface - Pulled 1" out Taped		
	off Well		

Thank You -- We appreciate your business!

Rec'd. by \_\_\_\_\_

TERMS: Account due upon receipt of services. A 1 1/2% Service Charge, which is an annual percentage rate of 18% will be charged to accounts after 30 days.

32884

RECEIVED  
 KANSAS CORPORATION COMMISSION

JUN 25 2010

CONSERVATION DIVISION  
 WICHITA, KS