

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 9408 Name: Trans Pacific Oil Corporation Address 1: 100 S Main Ste 200 Address 2: City: Wichita State: KS Zip: 67202 + 3735 Contact Person: Glenna Lowe Phone: (316) 262-3596 Type of Well: (Check one) [X] Oil Well [] Gas Well [] OG [] D&A [] Cathodic [] Water Supply Well [] Other: [] SWD Permit #: [] ENHR Permit #: [] Gas Storage Permit #: Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [] No Producing Formation(s): List All (If needed attach another sheet)

API No. 15 - 053-20117-00-00 Spot Description: -SW SW NE Sec. 21 Twp. 14 S. R. 10 [] East [X] West 2310 3081 Feet from [X] North [X] South Line of Section 2310 2316 Feet from [X] East [] West Line of Section Footages Calculated from Nearest Outside Section Corner: [X] NE [] NW [] SE [] SW County: Ellsworth Lease Name: Vopat D Well #: 1 Date Well Completed: The plugging proposal was approved on: by: Jeff Klock (KCC District Agent's Name) Plugging Commenced: 4/27/11 Plugging Completed: 4/28/11

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Includes data for Surface (8.625, 276, 175 Sacks Cement) and Production (4.5, 2174, 450 Sacks Cement).

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing to 2700' & pumped 25 sacks cement & 100# hulls. Pulled tubing and perforated at 1200', 900' & 325'. Ran tubing to 1200' & pumped 35 sacks cement, 3% cc & 100# hulls. Pulled to 900' & pumped 35 sacks cement, 3% cc & 100# hulls. Pulled to 325' & tagged cement at 400'. Circulated with 40 sacks cement to surface. Pulled tubing & topped off with 10 sacks cement. Pumped 95 sacks cement down 8 5/8" casing. Cut off 8 5/8" & 4 1/2" casings 4' below ground.

RECEIVED

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc MAY 11 2011 Address 1: 190 US Hwy 56 Address 2: BY City: Ellinwood State: KS Zip: 67526 Phone: (620) 727-3410

Name of Party Responsible for Plugging Fees: Trans Pacific Oil Corporation State of Kansas County: Sedgwick, ss. Gary Sharp (Print Name) [X] Employee of Operator or [] Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Gary Sharp

RECEIVED

MAY 12 2011

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC WICHITA