

RECEIVED

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION MAY 13 2011 OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD KCC WICHITA K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 05721 Name: Glacier Petroleum, Inc. Address 1: P.O. Box 577 Address 2: City: Emporia State: KS Zip: 66801 + 0577 Contact Person: J.C. Hawes Phone: (620) 342-1148 Type of Well: (Check one) [X] Oil Well [ ] Gas Well [ ] OG [ ] D&A [ ] Cathodic [ ] Water Supply Well [ ] Other: [ ] SWD Permit #: [ ] ENHR Permit #: [ ] Gas Storage Permit #: [ ] Is ACO-1 filed? [X] Yes [ ] No If not, is well log attached? [ ] Yes [ ] No Producing Formation(s): List All (If needed attach another sheet) Viola Depth to Top: 3248 Bottom: 3354 T.D. 3420

API No. 15 - 085-20032-00-00 Spot Description: C NW NE NW Sec. 22 Twp. 7 S. R. 13 [X] East [ ] West 278 4950 Feet from [X] North [X] South Line of Section 1.521 3630 Feet from [X] East [X] West Line of Section Footages Calculated from Nearest Outside Section Corner: [ ] NE [X] NW [ ] SE [ ] SW County: Jackson Lease Name: Hladky Well #: 4 Date Well Completed: 9/15/1984 The plugging proposal was approved on: 5/2/2011 (Date) by: Taylor Herman (KCC District Agent's Name) Plugging Commenced: 5/9/2011 Plugging Completed: 5/9/2011

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Row 1: Viola, Oil, Surface, 8 5/8", 300 ft, 0. Row 2: Long String, 5 1/2", 3420 ft, 1245 ft.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RIH w/ wireline bridge plug, plugged stopped at 2720 ft, set plug at 2720, dumped 2 sx cement on top plug w/ dump bailer, parted casing, pulled 1245 ft casing, circ 20 sx cement plug from 1245 ft. to 1190 ft. through 2 3/8 tubing, circ 35 sx cement plug from 350 ft to 250 ft. through 2 3/8" tubing, circ 20 sx cement plug from 60 ft. to surface. Consolidated Tk# 30503 dtd 5/9/11.

Plugging Contractor License #: 05721 Name: Glacier Petroleum, inc. Address 1: P.O. Box 577 Address 2: City: Emporia State: Kansas Zip: 66901 + 0577 Phone: (620) 342-1148 Name of Party Responsible for Plugging Fees: Glacier Petroleum, Inc. State of Kansas County, Lyon, ss. J.C. Hawes (Print Name) [ ] Employee of Operator or [X] Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Handwritten Signature]