

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 64709
Name: Schankie Well Service, Inc.
Address 1: PO Box 397
Address 2: 1006 SW Boulevard
City: Madison State: KS Zip: 66860 +0397
Contact Person: Cliff Schankie
Phone: (620) 437-2595
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Bartlesville Depth to Top: 1899' Bottom: 1953' T.D. 1989'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 073-21466 (0000)
Spot Description: SW NW NW
SW. NWNW Sec. 33 Twp. 23 S. R. 11 East West
990 Feet from North / South Line of Section
330 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Greenwood
Lease Name: Carson Well #: 16
Date Well Completed: 6-20-79
The plugging proposal was approved on: 4-1-11 (Date)
by: Mike Heffern, Dist #3 (KCC District Agent's Name)
Plugging Commenced: 4-1-11
Plugging Completed: 4-1-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			4 1/2"	1985'	None
			8 5/8"	100'	None

RECEIVED
MAY 13 2011
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Spot cement plug down 2 3/8" tubing 15sk @ 1840', Gel Spacer, Perforate 2 shots @ 800', Spot cement plug 15sk @ 800', Gel Spacer, Perforate 2 shots @ 150', Spot cement plug 55sk @ 160' to surface

Plugging Contractor License #: 6470 Name: Schankie Well Service, Inc.
Address 1: PO Box 397 Address 2: 1006 SW Boulevard
City: Madison State: KS Zip: 66860 +0397
Phone: (620) 437-2595

Name of Party Responsible for Plugging Fees: Schankie Well Service, Inc.
State of Kansas County, Greenwood, ss.
Randall Schankie, Secretary Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Handwritten Signature]

WELL LOG

Company Schankie Well Service, Inc.
 Farm Carson
 Well #16
 Location SW-NW- $\frac{1}{4}$ 33-23S-11 Greenwood County, Kansas
 Casing 100' of 8 5/8" cemented with 65 sacks
 1985' of 4 1/2" cemented with 100 sacks
 Commenced June 17, 1979
 Completed June 20, 1979
 Contractor Jackman & Jackman
 Production Testing
 Total Depth 1989'

RECEIVED
 MAY 13 2011
 KCC WICHITA

Soil & Clay	0	-	18
Lime	18		40
Shale & Shells	40		90
Plug & Cement	90		101
Lime & Shale	101		174
Shale & Shells	174		615
Shale	615		829
Lime	829		832
Water Sand	832		956
Lime	956		1090
Shale	1090		1238
Lime	1238		1550
Lime & Shale	1550		1601
Shale & Shells	1601		1899
Uper. Bart.	1899		1920
Shale	1920		1949
Sand Bart.	1949		1953
Shale	1953		1989

0' is 4' above ground level.

Box 884, Chanute, KS 66720
431-9210 or 800-487-8676

FIELD TICKET & TREATMENT REPORT

CEMENT API # 073-21466

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
04-01-11	1709	Carson #16	33	23 S	11 E	Greenwood
CUSTOMER Schankie Well Service Inc.			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS P.O. Box 397			485	Alan M.	(Brook Down)	
CITY Madison			479	J.P.		
STATE KS			520	Cliff		
ZIP CODE 66860						

JOB TYPE <u>plug oil</u>	HOLE SIZE _____	HOLE DEPTH _____	CASING SIZE & WEIGHT <u>4 1/2</u>
CASING DEPTH <u>1985'</u>	DRILL PIPE _____	TUBING _____	OTHER _____
SLURRY WEIGHT _____	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING _____
DISPLACEMENT _____	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____

REMARKS:

Spot 15 sk plug @ 1840
 Pump gel spacer
 Spot 15 sk plug @ 800
 Spot 55 sks plug @ 160' to Surface
 Rig down Job complete
 "Thanks Shannon & Crew"

RECEIVED
MAY 13 2011

KCC WICHITA

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405A	1	PUMP CHARGE	655.00	655.00
5406	15	MILEAGE	4.00	60.00
1131	85 sks	60/40 permit cement 4% gel	11.95	1015.75
1118B	207 #	Gel @ 4%	.20	41.40
1118B	500 #	10 sk Gel Spacer	.20	100.00
5407	2.58 tons	Ton mileage bulk truck	M/C	330.00
			sub total	2202.15
			7.5% SALES TAX	84.47
			ESTIMATED TOTAL	2286.62

Rev'n 3737

AUTHORIZATION [Signature] TITLE 240610 DATE 5-11-11

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.

CORNISH WIRELINE SERVICES, INC.

P.O. DRAWER H • CHANUTE, KS 66720

620-431-9308

INVOICE

Date of Invoice 4-5-11

Invoice # 15809

SOLD TO: SCHANKIE WELL SERVICE, INC.
P.O. BOX 397
MADISON, KS 66860

PLEASE RETURN ONE COPY OF
INVOICE WITH PAYMENT.

DATE OF SERVICE	TYPE OF SERVICE	AMOUNT
4-1-11	<p>CARSON #16 GREENWOOD COUNTY, KANSAS</p> <p>PERFORATED TO PLUG WITH 1-11/16" ALUMINUM SHOTS (1ST RUN)</p> <p>1 ADDITIONAL RUN</p> <p>2 SHOTS @ 800'</p> <p>2 SHOTS @ 150'</p> <p>AMOUNT DUE THIS INVOICE</p> <p><i>PO 4-18-11</i> <i>CK 21918</i></p> <p>THANK YOU. WE APPRECIATE YOUR BUSINESS!!</p> <p>TERMS: All invoices are due in full 30 days after invoice date. A FINANCE CHARGE of 1 3/4% (21% per annum) will be assessed after 30 days.</p>	\$475.00

RECEIVED
MAY 13 2011
KCC WICHITA