

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: COLT ENERGY, INC  
Address: P O BOX 388, IOLA, KS 66749  
Phone: (620) 365-3111 Operator License #: 5150  
Type of Well: OK DH Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 1/14/10 (Date)  
by: ALAN DUNNING (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
UPPER BARTLESVILLE Depth to Top: 762 Bottom: 766 T.D. \_\_\_\_\_  
MIDDLE BARTLESVILLE Depth to Top: 780 Bottom: 804 T.D. \_\_\_\_\_  
LOWER BARTLESVILLE Depth to Top: 880 Bottom: 887 T.D. 900

API Number: 15 - 205-27,813 100 00 ?  
Lease Name: WEST  
Well Number: A5  
Spot Location (QQQQ): SW SE NE SW NE SW NE  
2820 Feet from  North  South Section Line  
1490 Feet from  East  West Section Line  
Sec. 27 Twp. 30 S. R. 16  East  West  
County: WILSON  
Date Well Completed: DRY/PLUGGED  
Plugging Commenced: 3/5/10  
Plugging Completed: 3/5/10

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
SURFACE				7"	21.75	10SXS

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

3/5/10 FINNEY DRILLING COMPANY RUN TO 900' TD WITH DRILL PIPE. CONSOLIDATED OIL WELL SERVICES  
ESTABLISHED CIRCULATION TO 900' PUMPED 25SXS CEMENT@900 FINNEY PULLED DRILL PIPE UP TO 700' CONSOLIDATED PUMPED  
10SXS CEMENT FINNEY PULLED DRILL PIPE TO 250' CONSOLIDATED PUMPED 80SXS CEMENT TO SURFACE. FINNEY PULLED DRILL PIPE &  
TOPPED WELL OFF TOTAL 115SXS CEMENT USED WELL PLUGGED TO SURFACE

Name of Plugging Contractor: CONSOLIDATED OIL WELL SERVICES License #: 31440  
Address: P O BOX 884 CHANUTE, KS 66720  
Name of Party Responsible for Plugging Fees: COLT ENERGY, INC  
State of KANSAS County, ALLEN, ss.  
DENNIS KERSHNER

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Dennis Kershner  
(Address) PO Box 388, Iola, Ks. 66749

SUBSCRIBED and SWORN TO before me this 3<sup>rd</sup> day of May, 2010  
Shirley A. Stotler My Commission Expires: 1-20-2012  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 05 2010  
5-5-10  
CONSERVATION DIVISION  
WICHITA, KS



**CONSOLIDATED**  
Oil Well Services, LLC

**ENTERED**

TICKET NUMBER 23946

LOCATION Eureka

FOREMAN Steve D Neal

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

**FIELD TICKET & TREATMENT REPORT**  
**CEMENT**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
3-5-10	1828	West A-5				Wilson
CUSTOMER			TRUCK #			
MAILING ADDRESS			DRIVER			
CITY			TRUCK #			
STATE			DRIVER			
ZIP CODE						

JOB TYPE PTA HOLE SIZE 5 7/8 HOLE DEPTH 900' CASING SIZE & WEIGHT \_\_\_\_\_  
 CASING DEPTH \_\_\_\_\_ DRILL PIPE 2 7/8 TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
 SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING \_\_\_\_\_  
 DISPLACEMENT \_\_\_\_\_ DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE \_\_\_\_\_

REMARKS: Safety Meeting: Rig up to 2 7/8 Drill pipe. Plug well As Follow:

25 SKS AT 900'  
10 SKS AT 700'  
80 SKS 250 to Surface  
115 SKS 60/40 Poz mix 4 1/2 gal

Thank you

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405N	1	PUMP CHARGE	900.00	900.00
5406	40	MILEAGE	3.55	142.00
1131	115 SKS	60/40 Poz mix Cement	11.00	1265.00
1118A	395#	Gel 4 1/2	.17	67.15
5407		Ten Mileage Bulk Truck	MIC	305.00
RECEIVED KANSAS CORPORATION COMMISSION				
MAY 05 2010				
CONSERVATION DIVISION WICHITA, KS				
			Subtotal	2679.15
			SALES TAX	10.61
			ESTIMATED TOTAL	2749.76

Flavin 3737

033001

AUTHORIZATION Witness by Glen

TITLE Co. Rep

DATE  
SCANNED  
3/12/10 AD