

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5003
Name: McCoy Petroleum Corporation
Address 1: 8080 E. Central, Suite #300
Address 2:
City: Wichita State: KS Zip: 67206-2366
Contact Person: Brent Reinhardt
Phone: 316-636-2737
Type of Well (Check One): ~~Oil Well~~ Gas Well O&G D&A Cathodic
 Water Supply Well Other: SWD Permit #:
 ENHR Permit #: Gas Storage Permit #:
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Miss Depth to Top: 4975 Bottom: 4984 T.D. 4984
Stotler Depth to Top: 3474 Bottom: 3480 T.D. 3480
Depth to Top: Bottom: T.D.

API Number 15-097-21502 00 01
Spot Description: C NE NE Sec 29 Twp 30 S. Rng. 18 East West
660 3060 Feet from North / South Line of Section
660 1820 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Kiowa
Lease Name: COBB "A" #1-29
Date Well Completed: 4/23/03
The plugging proposal was approved on: 3/15/10 (Date)
by: Steve Durant (KCC District Agent's Name)
Plugging Commenced: 3/29/10
Plugging Completed: 3/31/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	727'	0
		Production	4 1/2"	5103'	2480'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

3/31/10: MIRU. Cut surface off 4' below ground. Sand was at 3425'. Bailed 45 sacks cement with bailer. Ripped casing at 2480' and came free. Pulled casing up to 740'. Pumped 50 sacks (15gel, 3% CC) with 100# hulls. Pulled to 300'. Pumped 50 sacks with 100# hulls. Pulled to 40' and pumped 20 sacks cement to surface. Topped off with 10 sacks.

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc.
Address 1: 190th US 56 Highway Address 2:
City: Ellinwood, State: KS Zip: 67526-8911
Phone: 620-727-3409

Name of Party Responsible for Plugging Fees: McCoy Petroleum Corporation
State of Kansas County, Sedgwick, ss.

Scott Hampel - Vice President, Production Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Scott Hampel

RECEIVED
KANSAS CORPORATION COMMISSION

APR 26 2010
4-26-10
CONSERVATION DIVISION
WICHITA, KS

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202