

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 31790
Name: Fremont Exploration, Inc.
Address 1: 12412 St. Andrews Drive
Address 2: _____
City: OKC State: OK Zip: 73120
Contact Person: Tom Conroy
Phone: (405) 936 0012
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 119-20910-00-00
Spot Description: _____
NWSE-SE Sec. 16 Twp. 32 S. R. 26 East West
1100 Feet from North / South Line of Section
1300 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Meade
Lease Name: Lauppe Well #: 16-1
Date Well Completed: _____
The plugging proposal was approved on: 2-16-10 (Date)
by: Eric MacLaren (KCC District Agent's Name)
Plugging Commenced: 2-25-10
Plugging Completed: 3-1-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8 5/8	995	—
			2 7/8	5650	2317

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

2 7/8 was stuck below 2300. Shot loose @ 2317 pull + inspect, ran back to 2317. Mixed 200 lb. hulls + 50 sx cmt stub plug from 2317 to 2167. Tag plug @ 2180. 50 sx plug 1980 to 1830 50 sx 1020 to 870 40 sx 600 to 480 10 sx 40 to 0 Capped 8 5/8 3 ft. below G.L.

Plugging Contractor License #: 31151 Name: Sargent + Horton Plugging Inc.
Address 1: Rt 1 Box 49 BA Address 2: _____
City: Tyrone State: OK Zip: 73951 + 9731
Phone: (580) 854 6515
Name of Party Responsible for Plugging Fees: Fremont Exploration, Inc.
State of Oklahoma County, Oklahoma, ss.
Tom Conroy Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Tom Conroy

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAR 26 2010
KCC WICHITA