

RECEIVED

MAR 01 2010

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION KCC WICHITA WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 5208 Name: ExxonMobil Oil Corporation Address 1: PO Box 4358 Address 2: City: Houston State: TX Zip: 77210 Contact Person: Richard Lewis Phone: (620) 544-5527 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENR Permit #: Gas Storage Permit #: Is AGG-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (if needed attach another sheet) Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API No. 15 - 189-20440-00 01 Spot Description: C-SENE Sec. 20 Twp. 32 S. R. 32 East West 1982 Feet from North South Line of Section 661 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Stevens Lease Name: Holt Unit Well #: 3 Date Well Completed: 5-12-79 The plugging proposal was approved on: 2-2-10 (Date) by: Jack MacLasky (KCC District Agent's Name) Plugging Commenced: 2-9-10 Plugging Completed: 2-10-10

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Casing, Size, Setting Depth, Puffed Out). Data includes casing sizes of 8 5/8 and 5 1/2, setting depths of 1778 and 6500, and puffed out depth of 1812.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP + 20' cmt. 5760 to 5740 CIBP @ 2000 no cmt. Pres. test 5 1/2. Shot 5 1/2 loose @ 1812. Circ. hole w/mud & mixed 50 sx plug from 1810 to 1660 40 sx plug 650 to 530 10 sx 40 to 0 Capped 8 5/8 3 ft. below G.L.

Plugging Contractor License #: 31151 Name: Sargent & Horton Plugging Inc. Address 1: Rt 1 Box 49 BA Address 2: City: Tyrone State: OK Zip: 73951 + 9731 Phone: (580) 854 6515 Name of Party Responsible for Plugging Fees: EXXON MOBIL PRODUCTION Co. State of KANSAS County: STEVENS RICHARD B. LEWIS - WORKOVER SUPT. Employee of Operator or Operator on above-described well

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: RB Lewis 2/26/10