

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-9-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5447
Name: Oxy USA, Inc
Address 1: P.O. Box 2528
Address 2: _____
City: Liberal State: KS Zip: 67905+
Contact Person: Kenny Andrews
Phone: (620) 629 4200
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Morrow Depth to Top: 5141 Bottom: 5204 T.D. 5580

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 081-21484 00 00
Spot Description: SE NW SW
NESE NW SW Sec. 18 Twp. 27 S. R. 34 East West
1836 Feet from North / South Line of Section
1275 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Haskell
Lease Name: Berger B Well #: 1
Date Well Completed: 7-29-03
The plugging proposal was approved on: 12-18-09 (Date)
by: Richard Lacy (KCC District Agent's Name)
Plugging Commenced: 12-18-09
Plugging Completed: 12-22-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8 5/8	1869	-
			4 1/2	5548	2537

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 500 lb. hulls + 20 sx cmt. to plug perfs from 5141 to 4941.
Shot & pulled 4 1/2 to 1900. Circ. hole w/mud & mixed 50 sx
plug from 1900 to 1750. Mixed 40 sx plug from 800 to 680
10 sx from 40 to 0. Capped 8 5/8 5 ft. below G.L.

Plugging Contractor License #: 31151 Name: Sargent + Horton Plugging Inc.
Address 1: Rt 1 Box 49 BA Address 2: _____
City: Tyrone State: OK Zip: 73951 + 9731
Phone: (580) 854 6515

Name of Party Responsible for Plugging Fees: Oxy USA Inc. 1701 N. Kansas P.O. Box 2528 Liberal, KS. 67905
State of Kansas County: Seward, ss.
Kenny Andrews Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Kenny Andrews

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION

APR 01 2010

CONSERVATION DIVISION
WICHITA, KS



OXY USA Inc.

1701 N. Kansas, Liberal, KS 67901
P.O. Box 2528, Liberal, KS 67905-2528

March 29, 2010

Kansas Corporation Commission
Wichita State Office Bldg.
130 South Market, Room 2078
Wichita, Kansas 67202

OXY USA Inc.
Re: Well Plugging Record (CP-4)
Re: Closure of Surface Pond (CDP-4)

Berger B-1
API # 15-081-21484
Section 18-27S-34W SW/4
Haskell, Co. Ks.

To Whom It May Concern:

Please find enclosed the Well Plugging Record (CP-4) for the subject well. Also, please find the pit closure form (CDP-4).
Thanks for your help.

If there are any questions or you require further information, please contact me at the above address or by
Phone at (620) 629 - 4232.

Sincerely,

Kenny L. Andrews
Well Operations Lead
OXY USA Inc.
Hugoton Asset
Liberal, Kansas

RECEIVED
KANSAS CORPORATION COMMISSION
APR 01 2010
CONSERVATION DIVISION
WICHITA, KS