

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5004
Name: Vincent Oil Corporation
Address 1: 155 N. Market, Suite 700
Address 2: _____
City: Wichita State: KS Zip: 67202 + 1821
Contact Person: M.L. Korphage
Phone: (316) 262-3573
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. 4610
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 097-20784-00-00
Spot Description: NW-NE
_____ NW-NE Sec. 24 Twp. 27 S. R. 16 East West
660 4685 Feet from North / South Line of Section
1980 1994 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Kiowa
Lease Name: Butler-Thompson Well #: 3-24
Date Well Completed: 8/28/1981
The plugging proposal was approved on: _____ (Date)
by: Steve Durrant (KCC District Agent's Name)
Plugging Commenced: 2/25/2010
Plugging Completed: 3/01/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface Casing	8 5/8"	365'	0
		Production Casing	4 1/2"	4603'	2270'

RECEIVED
APR 07 2010
4-7-10
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Blew down gas, fluid at surface; Tied onto 4 1/2" casing and pumped 30 sx of cement & 250# hulls, displaced with 65 bbls of water, SIP 300#; Tagged cement at 4150'; Ripped casing at 2610'; 2430', and 2270'; Pulled casing to 1050', pumped 15 sx gel, 50 sx cement, & 100# hulls; Pulled casing to 390', pumped 50 sx cement & 100# hulls; Pulled casing to 40', pumped 20 sx cement to surface. [Used a total of 150 sx 60/40 Poz (4% Gel), Quality Oilwell Cementing Ticket #3998].

DK

Plugging Contractor License #: 31925 Name: Quality Well Service
Address 1: 190 th US 56 Highway Address 2: _____
City: Ellinwood State: Kansas Zip: 67526 + _____
Phone: (620) 727-3410
Name of Party Responsible for Plugging Fees: Vincent Oil Corporation
State of Kansas County, Sedgwick, ss.
M.L. Korphage Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: M.L. Korphage

QUALITY OILWELL CEMENTING, INC.

Phone 785-483-2025
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 3998

Date 3-1-10	Sec. 24	Twp. 27	Range 16	County Kiowa	State Ks	On Location	Finish 11:00
--------------------	----------------	----------------	-----------------	---------------------	-----------------	-------------	---------------------

Lease **Butler-Thompson** Well No. **3-24** Location

Contractor **Quality Well Ser.** Owner

Type Job **PTA** To Quality Oilwell Cementing, Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.

Hole Size T.D. Charge To **Vince + oil Corp.**

Csg. **4 1/2** Depth Tbg. Size Depth Street

Tool Depth City State

Cement Left in Csg. Shoe Joint The above was done to satisfaction and supervision of owner agent or contractor.

Meas Line Displace **CEMENT**

EQUIPMENT

Amount Ordered **150SK. 60/40 4%**

Pumptrk 6	No.	Cementer Dave	Common
		Helper	

Bulktrk 11	No.	Driver Rich	Poz. Mix
		Driver	

Bulktrk	No.	Driver James	Gel.
		Driver	

JOB SERVICES & REMARKS

Remarks: **2-25-10. Truck #5 set** Calcium

pumped 30sks @ 56# holls down. Halls **450 #**

4 1/2 csg. 300 psi shut in. Salt

1st pumped 15gel Saks 100# Halls Flowseal

@ 1030 **15gel on side.**

2nd pumped Saks @ 390' Handling

3rd pumped 20sks @ 40' to surface Mileage **20**

FLOAT EQUIPMENT

Guide Shoe

Centralizer

Baskets

AFU Inserts **4 1/2 wiper ply**

Pumptrk Charge

Mileage

Tax

Discount

Total Charge

X Signature **Daniel Brady**

RECEIVED
APR 07 2010

KCC WICHITA

