

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33168
Name: Woolsey Operating Co. L.L.C.
Address 1: 125 N. Market, Suite 1000
Address 2: _____
City: Wichita State: KS Zip: 67202 + 1729
Contact Person: Carl Durr
Phone: (620) 886-5606
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: 5121 Bottom: 5144 T.D. 5146

Depth to Top: 5148 Bottom: 5160 T.D. 5420

Depth to Top: 5465 Bottom: 5483 T.D. _____

API No. 15 - 033-21474-00-01
Spot Description: _____
NW SE SW Sec. 32 Twp. 31 S. R. 17 East West
990 Feet from North / South Line of Section
2,310 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Comanche
Lease Name: York Well #: B-1
Date Well Completed: _____
The plugging proposal was approved on: 6/7/2011 (Date)
by: Mike Maier (KCC District Agent's Name)
Plugging Commenced: 6/7/2011
Plugging Completed: 6/8/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Conductor	20"	77'	None
		Surface	10 3/4	253'	None
		Production	4 1/2	5714	1400

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 5070', spot 2sx cement with dump bailer on plug, lay down casing, run tubing 1st 1150', pump 12sx gel, 50sx 60/40 POZ 4% gel, 2nd 300', 70sx cement, 3rd 60', 25sx circulate to surface, check conductor pipe for fill 6' from surface
6/10 - measure surface 140', redi mix 2 1/2 yards cement down surface

RECEIVED

JUN 27 2011
6-27-11
KCC WICHITA

Plugging Contractor License #: 5105 Name: CLARKE CORPORATION
Address 1: 107 W. FOWLER Address 2: P.O. BOX 187
City: MEDICINE LODGE State: KS Zip: 67104 + _____
Phone: (620) 886-5665
Name of Party Responsible for Plugging Fees: Woolsey Operating
State of KANSAS County, BARBER, ss.
MARK MORGENSTERN Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mark Morgenstern