

State of Kansas



FORM CP-2

15-051-22633-60-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Thomas W. Wiesner of Helberg Oil Company has this date requested permission to plug the following described well:

Operator's Full Name: Thomas W. Wiesner

Complete Address: 3007 Indian Trail, Hays, Ks. 67601

Lease Name: Thomas Dean Walters Well No. #1

Location: 280' East of SE/SW/SE Sec. 4 Twp. 13 Rge. 17 (E) (W)

County: Ellis Total Depth: 3690'

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereafter indicated:

Mr. Thomas W. Wiesner was instructed to plug the well as follows:

8 5/8"-205 sp. cuc. w/130 sacks common-2% Gel.-3% Cal. Cl.

Ordered 125 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

1st plug @ 780' w/70 sacks of cement

2nd plug @ 210' w/40 sacks of cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks of cement.

5 sacks of cement in rat hole.

Very truly yours,

OCT 19 1981
10-19-81
CONSERVATION DIVISION
Wichita, Kansas

[Signature]
Conservation Division Agent