



15-051-21341-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 06 1977

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Lingreen of Revlin Drlg. has this

date requested permission to plug the following described well:

Mr. Lingreen guarantees payment of the plugging fee.

Operator's full Name: Black-Stem Investors

Complete Address: Box 39, Catherine Rt., Hays, Ks.

Lease Name: Befort Well No. 1

Location: 660' FEL & 660' FNL of Sec. 27 Twp. 13 Rge. (E)(W) 20

County: Ellis Total Depth 3830' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Lingreen was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 720' thru drill

pipe. Heavy mud to 215' set 20 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey
Conservation Division Agent