



15-051-20176-00-00

ROBERT B. DOCKING Governor  
 WILLIAM L. MITCHELL Chairman  
 JAMES O. GREENLEAF Commissioner  
 DALE E. SAFFELS Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

**VERBAL PERMIT FORM**  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 13 1967  
 12-13-67  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Moore of C & G Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: Dane G. Hansen Trust

Complete Address: Logan, Kansas

Lease Name: Storm "B" Well No. 2

Location: S/2 SE NE Sec. 34 Twp. 13 Rge. 20 (E)(W) X

County: Ellis Total Depth 3863 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Moore was instructed to plug the well as follows:

Gun pits, Circulate heavy mud, set cementing plug at 800' and displace  
100 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and  
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Leo J. Mussey  
 Conservation Division Agent