



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

15:051-23109-00-00

Dear Sir:

Mr. Zorn of Shields Oil Co., Inc. has this

date requested permission to plug the following described well:

Operator's Full Name: Shields Oil Producers, Inc.

Complete Address: Shields Bldg., Russell, Ks. 67665

Lease Name: Engel Well No. 1

Location: SE SW NE Sec. 35 Twp. 13 Rge. 20 (E) (W)

County: Ellis Total Depth: 3900'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Zorn was instructed to plug the well as follows:

8 5/8" - 268' SP. case w/ 168 sacks common - 2 7/8" Gel. - 3 7/8" Col. Cl.

Ordered 150 sacks 50 posmix - 4 7/8" Gel - 3 7/8" Col. Cl. & 8 5/8" plug. spot w/ drill stem w/

heavy mud between all plugs. 1st plug @ 720' w/ 80 sacks.

2nd plug @ 275' w/ 40 sacks.

3rd plug - solid bridge of balls & plug @ 40' w/ 10 sacks.

Circulate 10 sacks in rat hole & 10 sacks in mouse hole

Very truly yours,

Gilbert R. Scheetz  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 23 1982  
8-23-82  
CONSERVATION DIVISION  
Wichita, Kansas