


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

15-167-20328-00-00
Form CP-4

NORTH



Locate well correctly on above
Section Plat

Russell

County. Sec. 20 Twp. 14 Rge. 11 West (W)

Location as "NE/CNWxSWx" or footage from lines. SE/4 SW/4 SW/4

Lease Owner Carl Boxberger

Lease Name JACOBS

Well No. 1

Office Address Box 474 - Great Bend, Ks. 67530

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 8 19 69

Application for plugging filed June 8 19 69

Application for plugging approved June 8 19 69

Plugging commenced June 8 19 69

Plugging completed June 8 19 69

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan

Producing formation Depth to top Bottom Total Depth of Well 3200 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

RECEIVED
STATE CORPORATION COMMISSION
JUN 11 1969
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole full of heavy mud.
Set plug at 400' - 40 sacks cement thru drill pipe.
Come up hole to 240' - ~~20 sacks~~ 20 sacks cement thru d.p.
Come up hole to 40' - good plug-good bridge 1/2 sk hulls, 10 sks. cement .
2 sacks cement in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Address

STATE OF Kansas, COUNTY OF Barton, ss.

Larry Curtis

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis


Box 823 - Great Bend, Ks. 67530

(Address)

Subscribed and sworn to before me this 9th day of June, 19 69

April 11, 1970

Notary Public.



15-167-20328-00-00

W E L L L O G

DATE COMMENCED: June 1, 1969
DATE COMPLETED: June 8, 1969

Carl Bomberger
JACOB # 1
SE/4 SW/4 SW/4
Sec. 20-14-11W
Russell, Co. Kansas

ELEVATION: 1676 K. B.

0 -	12'	Clay
12 -	25'	Sand
25 -	126'	Clay & Shale
126 -	250'	Shale & Shells
250 -	335'	Shale
335 -	522'	Red Bed
522 -	555'	Anhydrite
555 -	942'	Shale & Shells
942 -	1114'	Salt Stringers & Shale
1114 -	1445'	Shale & Shells
1445 -	1759'	Lime & Shale
1759 -	2462'	Shale & Lime
2462 -	2708'	Lime
2708 -	2711'	Shale
2711 -	2728'	Lime & Shale
2728 -	2742'	Lime
2742 -	2794'	Shale
2794 -	2809'	Br. Lime & Shale
2809 -	3098'	Lime
3098 -	3185'	Conglomerate
3185 -	3200'	Dolomite
	3200'	T. D.

Formation Data
Anhydrite 522
Grand Haven 2110
Tarkio 2190
Topeka 2462
Heebner 2708
Toronto 272
Douglas 2742
B. Lime 2794
B. K. C. 3098
Arbuckle 3185
R. T. D. 3200

SURFACE PIPE: Set 250'
of 8 5/8 with 175 lbs.
cement.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss.

Larry Curtis of lawful age, does swear and state that
the facts and statements herein contained are true and correct to the
best of his knowledge.

RECEIVED
STATE CORPORATION COMMISSION
JUN 11 1969
CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn to before me this 9TH day of June, 1969

My Comm. Expires:
4-11-70

Martha M. Hogue
Notary Public

