


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-167-00134-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Russell County. Sec. 16 Twp. 14 Rge. 11 (1/2) W (W)

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines SE NE SE  
Lease Owner Coppinger Drilling, Inc.  
Lease Name J Wikle Well No. 1  
Office Address 320 Union Natl Bk Bldg., Wichita  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed July 7, 1956 19  
Application for plugging filed same 19  
Application for plugging approved same 19  
Plugging commenced same 19  
Plugging completed same 19  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Milton Galyardt  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3245 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	227	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud laden fluid to 225' of top;  
Pushed plug to 225' - cemented with 20 sax -  
Filled hole to 40' of top;  
Pushed plug to 40' of top;  
Cemented with 10 sax cement.

RECEIVED  
COMMISSION  
DIVISION  
07-10-56

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Coppinger Drilling, Inc.  
Address Wichita, Ks.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
W. J. Coppinger of Coppinger Drilling, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. J. Coppinger  
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 9th day of July, 1956  
My commission expires March 7, 1960  
Mayree Broadus  
(Mayree Broadus) Notary Public.

PLUGGING  
FILE SEC. 16 T. 14 R. 11W  
BOOK PAGE 78 LINE 31

15-167-00134-00-00

State Corp.

DRILLERS LOG

Coppinger Drilling, Inc.  
Wichita, Kansas

Wikle #1 -  
SE NE SE Sec. 16-14s-11w  
Russell County, Kansas

Drilling commenced 6-26-56  
Drilling completed 7-7-56  
Elevation: 1706 RB  
1704 DF  
1702 GL

Casing Record  
8-5/8" set at 227 w/125 sax cement

Native dirt	45
Sand	55
Clay	227
Clay, sand & pyrite	295
Gyp rock	325
Shale and pyrite	410
Red bed and shells	460
Red bed	540
Anhydrite	570
Red bed, shale & shells	900
Red bed and shale	1010
Salt and shale	1150
Shale and lime	1515
Lime	1575
Sandy shale	1600
Lime	1830
Red shale	1850
Lime	1900
Shale	1925
Lime and shale	1990
Shale	2195
Shale and lime	2765
Shale	2821
Lime	3100
Shale and lime	3199
Chert and lime	3220
Arbuckle lime	3245
R T D	3245'

<u>Sample tops</u>	
Heebner	2733
Toronto	2750
Brown Lime	2821
Lansing	2836
Marmaton	3115
Conglomerate	3173
Arbuckle	3215
R T D	3245

Dry and abandoned.

State of Kansas,  
County of Sedgwick, ss.

<b>PLUGGING</b>
FILE SEC. 16 T. 14 R. 11 W
BOOK PAGE 79 LINE 31

I hereby certify that the foregoing is a true and correct log of the Wikle #1 drilled at the above location by Coppinger Drilling, Inc., to the best of my knowledge and belief.

Lee Poulsen  
Lee Poulsen, Geologist

Subscribed and sworn to before me, a notary public, this 9th day of July, 1956.

My commission expires: March 7, 1960

Mayree Broadus  
(Mayree Broadus) Notary Public