

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-167-2252-00-00

LEASE NAME Georgina M. Eschbaugh

WELL NUMBER 1-11

SPOT LOCATION C SE SE

SEC. 11 TWP. 14 SRGE. 11 W (S) or (W)

COUNTY Russell

Date Well Completed _____

Plugging Commenced 3-25-86

Plugging Completed 5-12-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kelso Casing Pulling Bought F/Davies & Company,
Inc.

ADDRESS P.O. Box 347 Chase, Ks. 67524

PHONE # (316) 938-2457 OPERATORS LICENSE NO. 6050

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 2370'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	318'	none
				4-1/2"	2369'	1593'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 2125' and 4 sacks cement. Shot pipe @1725', 1593', pulled a total of 41 joints of 4-1/2" casing. Plugged surface with 3 hulls and 100 sacks econolite w/2 hulls. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 14th day of May, 19 86

My Commission expires:



Irene Hoover
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
MAY 16 1986
05-16-86
CONSERVATION DIVISION
Wichita, Kansas

PROPERTY MANAGEMENT
LEASE OPERATIONS

A SERVICE OF THE OIL INDUSTRY

WELL COMPLETIONS
RE-COMPLETIONS

15-167-21252-00-00

C. E. (ED) LEITH
OPERATIONS
427 UNION CENTER BLDG.
WICHITA, KANSAS 67202
TELEPHONE 316-265-3491

*8 1/2 @ 318
Cement crew
TD 2370*

DAVIES & COMPANY, INC.
1304 Philtower Building
Tulsa, Oklahoma 74103

GEORGINA M. ESCHBAUGH NO. 1-11
C SE SE Sec. 11-14S-11W
Russell County, Kansas

CASING RECORD

11-22-78

Ran, set & cemented 81 jts. 2369' - 4 1/2" OD 9.5# 8rd. Casing @ 2369' w/
150 sacks 60/40 Pozmix Cement 10% salt - 12 1/2#/sack Gilsonite - 3/4-1% CFR-2
Plug down 10:45 AM 11-22-78.

Shoe joint 38' long - Float @ 2331'

Casing Centralizers: 2368', 2260', 2148' and 2040'

Total Depth 2370'

NOTE: Good returns during cementing -

DIRECTIONS: I-70 & Wilson exit - 1/2 South - 2 1/2 West - South Side.

PROPERTY MANAGEMENT
LEASE OPERATIONS

A SERVICE OF THE OIL INDUSTRY

WELL COMPLETIONS
RE-COMPLETIONS

C. E. (ED) LEITH
OPERATIONS
427 UNION CENTER BLDG.
WICHITA, KANSAS 67202
TELEPHONE 316-265-3491

DAVIES & COMPANY, INC.
1304 Philtower Building
Tulsa, Oklahoma 74103

ESCHBAUGH LEASE WELL NO. 1-11
C SE SE Sec. 11-14S-11W
Russell County, Kansas

COMPLETION RECORD

SUMMARY:

Total Depth : 2370'
Plug Back Total Depth: 2305'
Perforations: 2208-24 and 2183-87'
Stimulation: 15000# Sand + Foam Frac.
Tubing: 71 jts. 2179' - 2-3/8"
Seating Nipple: 2-3/8" x 12" Std. Set @ 2180'

*So - I-70 - No Wilson Rd
2 1/4 west - No side*

add 2 1/2 to 8

RECEIVED
STATE CORPORATION COMMISSION

MAR 3 1986

CONSERVATION DIVISION
Wichita, Kansas