


15-167-20533-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

WELL PLUGGING RECORD



Russell County. Sec. 11 Twp. 14 Rge. 11 (E) (W)
Location as "NE/CNW/SE" or footage from lines. SW SE SE
Lease Owner Albert Borell
Lease Name Eschbaugh B#2 Well No. _____
Office Address Wilson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1/20/76 _____ 19____
Plugging completed 1/23/76 _____ 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2988 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	292	none
				5 1/2"	2479	1852'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran sand to 2150' and dumped 5 sacks cement. Shot pipe at 1836', pulled 59 joints. Pumped 3 sacks hulls, 25 sacks gel and 100 sacks cement.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of January, 19 76

My commission expires _____
NOTARY PUBLIC
MARGARET MELCHER
Rice County, Ks.
My Comm. Exp. Feb. 15, 1979

Margaret Melcher
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
JAN 30 1976
CONSERVATION DIVISION
Wichita, Kansas

15-167-20533-00-00

DRILLERS LOG

NO. 2. Eschbaugh "B"

CASING RECORD:

COMPANY: Albert Borell

DESCRIPTION:

8 5/8" @ 292'
w/175 sx cement

CONTRACTOR: Red Tiger Drilling Co.

SW SE SE
11-14S-11W
Russell County,
Kansas

5 1/2" @ 2479'
w/100 sx cement

COMMENCED: April 17, 1972

COMPLETED: April 24, 1972

ELEVATION:

TOTAL DEPTH: 2988'


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale & Sand	0	293	
Shale, Red Bed & Sand	293	579	
Anhydrite	579	607	
Shale & Red Bed	607	880	
Shale & Shells	880	1300	
Shale & Lime	1300	2195	
Shale, Lime & Sand	2195	2319	
Shale & Lime	2319	2730	
Lime	2730	2790	
Lime & Shale	2790	2885	
Lime	2885	2988	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jim Farrice
Jim Farrice

Subscribed and sworn to before me this 26th day of April, 1972.



Virginia K. Albert
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

JUL 29 1975

CONSERVATION DIVISION
Wichita, Kansas