

15-167-21132-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Russell County, Sec. 10 Twp. 14 Rge. 11 X/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
50' N & 150' C C NW NE

Lease Owner Custom Oil Exploration  
Lease Name Doubrava Well No. 1

Office Address Box 305, Chase, KS 67524  
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed 12-29 19 77

Application for plugging filed 12-29 19 77

Application for plugging approved 12-29 19 77

Plugging commenced 12-29 19 77

Plugging completed 12-29 19 77


Reason for abandonment of well or producing formation  
Dry Hole

If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin  
Producing formation Depth to top Bottom Total Depth of Well 3060

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above  
Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	250	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- Mud laden fluid 3060 to 420'
- 40 sks cement @ 420'
- 20 sks cement @ 240'
- 10 sks cement @ 40'
- 2 sks cement in rat hole

RECEIVED  
STATE CORPORATION COMMISSION

DEC 30 1977

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

STATE OF KANSAS COUNTY OF RUSSELL, ss.


Joe K. Branum (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe K. Branum  
Box 506, Russell, KS 67665  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of December, 1977

Patricia L. Clark  
Notary Public.

My commission expires October 2, 1979



15-167-21132-00-00

EMPHASIS OIL OPERATIONS

P. O. Box 506

Russell, Kansas 67665

DRILLERS LOG

OPERATOR: Custom Oil Exploration  
Box 305  
Chase, KS 67524

CONTRACTOR: Emphasis Oil Operations  
Box 506  
Russell, KS 67665

LEASE: Doubrava WELL: #1

LOCATION: 50' N & 150' E, C NW NE  
Section 10-14S-11W  
Russell County, Kansas

Total Depth: 3060'

Elevation: 1773' K.B.

Commenced: 12-19-77

Completed: 12-29-77

Casing: 8-5/8" @ 250'

Status: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Post Rock & Shale	255	Shale & Lime	2525
Hard Sand & Shale	540	Lime & Shale	2840
Shale & Sand	605	Shale & Lime	2955
Anhydrite	637	Lime & Shale (R.T.D.)	3060
Shale & Lime	1625		
Lime & Shale	2422		

RECEIVED  
STATE CORPORATION COMMISSION

DEC 30 1977

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
COUNTY OF RUSSELL) ss

I, Joe K. Branum, of Emphasis Oil Operations, state that the above and foregoing is a true and correct log of the above captioned well.

*Joe K. Branum*  
Joe K. Branum

Subscribed and sworn to before me this 29th day of December, 1977.

My Commission Expires: October 2, 1979.

*Patricia L. Clark*  
Notary Public

