

RECEIVED

FEB 08 2010

Form CP-4

March 2009

Type or Print on this Form

Form must be Signed

All blanks must be Filled

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

KCC WICHITA

OPERATOR: License #: 5278 Name: EOG Resources, Inc. Address 1: 3817 NW Expressway Address 2: Suite 500 City: Oklahoma City State: OK Zip: 73112 + 1483 Contact Person: Candy Driscoll Phone: (405) 246-3140 Type of Well: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): Basal Chester Depth to Top: 5672' Bottom: 5690' T.D. 5940'

API No. 15 - 025-21295 (00-00) Spot Description: N2 NE NW Sec. 11 Twp. 34 S. R. 24 East West 330 Feet from North / South Line of Section 1,980 Feet from East / West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Clark Lease Name: Gardiner 11 Well #: 2 Date Well Completed: 7/13/2005 The plugging proposal was approved on: 1/25/2010 (Date) by: Steve Durant (KCC District Agent's Name) Plugging Commenced: 1/26/2010 Plugging Completed: 1/28/2010

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Rows include Basal Chester with Oil content and Surface/Production casing records.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Load casing w/ mud & set 4 1/2" 10K CIBP @ 5622', cap w/ 2 sks cement. Cut & pull 4 1/2" csg from 2416', Lay down 58 jts casing. Run tbg @ 1039' & pump 120 sks Class "C" cement up to 600', pull up hole w/ tbg @ 300' & spot 40 sks Class "C" cement up to 150', POH w/ tbg & top out 54' - 4' w/ 15 sks cement.

Plugging Contractor License #: 33338 Name: Orr Enterprises, Inc. Address 1: P.O. Box 1706 Address 2: City: Duncan State: OK Zip: 73534 + 1706 Phone: (580) 467-0258 Name of Party Responsible for Plugging Fees: EOG Resources, Inc. State of Oklahoma County, Oklahoma, ss. Candy Driscoll Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Candy Driscoll