

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5004
Name: Vincent Oil Corporation
Address 1: 155 N. Market, Suite 700
Address 2: _____
City: Wichita State: Ks Zip: 67202 + 1 8 2 1
Contact Person: M.L. Korphage
Phone: (316) 262-3573
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. 5100
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 083-21611-00-00
Spot Description: ~SE-NW-SE-SE
SE NW SE SE Sec. 24 Twp. 24 S. R. 26 East West
800 Feet from North / South Line of Section
720 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Hodgeman
Lease Name: Harms Well #: 1-24
Date Well Completed: 10-17-2009
The plugging proposal was approved on: 10/16/2009 (Date)
by: Steve Durrant (KCC District Agent's Name)
Plugging Commenced: 10/17/2009
Plugging Completed: 10/17/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
	RECEIVED KANSAS CORPORATION COMMISSION JAN 12 2010 CONSERVATION DIVISION WICHITA, KS	Surface Casing	8 5/8'	313'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hole filled with drilling mud, set cement plugs through drill pipe as follows: 50 sx at 1780'; 80 sx at 1020'; 40 sx at 570'; 40 sx at 330'; and a 20 sx plug at 60'. Plugged rathole with 30 sx and plugged mousehole with 20 sx. Used total of 280 sx of 60 / 40 POZ (4% Gel & 1/4# Flo-seal/sx). Allied Cementing Co. LLC Ticket # 33398

Plugging Contractor License #: 5929 Name: Duke Drilling Co., Inc.
Address 1: P.O. Box 823 Address 2: _____
City: Greatt Bend State: Kansas Zip: 67530 + _____
Phone: (620) 793-8366
Name of Party Responsible for Plugging Fees: Vincent Oil Corporation
State of Kansas County, Sedgwick, ss.
M.L. Korphage Employee of Operator or Operator on above-described well
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: M.L. Korphage

ALLIED CEMENTING CO., LLC. 33398

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

COPY

SERVICE POINT: Great Bend 45

DATE <u>10-17-09</u>	SEC. <u>24</u>	TWP. <u>24</u>	RANGE <u>26</u>	CALLED OUT	ON-LOCATION	JOB START <u>5:00 PM</u>	JOB FINISH <u>6:00 PM</u>
LEASE <u>Harms</u>		WELL# <u>1-24</u>		LOCATION <u>Hodgeman Co. line 2 North</u>		COUNTY <u>Hodgeman</u>	STATE <u>KS</u>
OLD OR <input checked="" type="radio"/> NEW (Circle one)				<u>12 west North into</u>			

CONTRACTOR <u>Duke 1</u>	OWNER <u>Vincent oil</u>
TYPE OF JOB <u>Rotary plug</u>	
HOLE SIZE <u>7 3/4</u>	T.D. <u>5100</u>
CASING SIZE	DEPTH
TUBING SIZE	DEPTH
DRILL PIPE <u>4 1/2</u>	DEPTH <u>1780</u>
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT <u>19 1/2 water 1788 lbs mud</u>	
EQUIPMENT	
PUMP TRUCK CEMENTER <u>Wayne - D</u>	
# <u>181</u>	HELPER <u>Alvin - R</u>
BULK TRUCK	
# <u>481</u>	DRIVER <u>Chris</u>
BULK TRUCK	
#	DRIVER

CEMENT			
AMOUNT ORDERED	<u>280 SX 60/40 4% Gel</u>		
<u>1/4 # #10 Seal</u>			
COMMON <u>168</u>	@ <u>13.50</u>	<u>2,268.00</u>	
POZMIX <u>112</u>	@ <u>7.55</u>	<u>845.60</u>	
GEL <u>10</u>	@ <u>20.25</u>	<u>202.50</u>	
CHLORIDE	@		
ASC	@		
<u>Flascol 15 #</u>	@ <u>245</u>	<u>183.75</u>	
	@		
	@		
	@		
	@		
	@		
HANDLING <u>293</u>	@ <u>2.25</u>	<u>659.25</u>	
MILEAGE <u>52/293/10</u>		<u>1,523.60</u>	
		TOTAL	<u>5,682.20</u>

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 12 2010

CONSERVATION DIVISION
WICHITA, KS

REMARKS:

1st plus 1780 mix 50SX 60/40 4% Gel
1/4 # #10 Seal Displace 5 water 1788 lbs Mud
2nd plus 1020 mix 80SX 60/40 4% Gel 1/4 #
Displace 8 BBLs at water 2nd plus 570
mix 40SX 60/40 4% Gel 1/4 # #10 Seal
Displace 4 BBLs at water 4th plus 330
mix 40SX 60/40 4% 1/4 # #10 Seal Displace 2 BBL
5th plus 60 mix 20SX 60/40 4% 1/4 # #10 Seal
Displace 1 BBL Rot mix 30SX Mouse 20SX
wash up Rig Down

CHARGE TO: Vincent oil

STREET _____

CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB	<u>1780</u>		
PUMP TRUCK CHARGE		1800.00	<u>991.00</u>
EXTRA FOOTAGE	@		
MILEAGE <u>52</u>	@ <u>7.00</u>	<u>364.00</u>	
MANIFOLD	@		
	@		
	@		
		TOTAL	<u>1355.00</u>

PLUG & FLOAT EQUIPMENT

_____	@		
_____	@		
_____	@		
_____	@		
_____	@		
		TOTAL	_____

To Allied Cementing Co., LLC.
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME Mike Godfrey

SIGNATURE Mike Godfrey

SALES TAX (If Any) _____

TOTAL CHARGES ~~1800.00~~ ~~1222.00~~

DISCOUNT ~~_____~~ IF PAID IN 30 DAYS